

745-2012 ADDENDUM 5

RIVERGATE OUTFALL GATE CHAMBER CONSTRUCTION AND UPGRADES

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID OPPORTUNITY

ISSUED: October 24, 2012
BY: Edmund Ho, P.Eng.
TELEPHONE NO. (204) 943-3178

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID OPPORTUNITY AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: A20120228

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read: The Submission Deadline is now 12:00 noon Winnipeg time, October 30, 2012.

PART E – SPECIFICATIONS

- Revise: D17.1 to read: If the Contractor fails to achieve Substantial Performance in accordance with the Contract by the day fixed herein for Substantial Performance, the Contractor shall pay the City one thousand dollars (\$1,000.00) per Calendar Day for each and every Calendar Day following the day fixed herein for Substantial Performance during which such failure continues.
- Revise: E12.3(b)(vii) to read: Install groundwater depressurization well and all pumping required to locally draw down the groundwater elevation to the underside elevation of the proposed construction excavation.
- Revise: E12.3(b)(viii) to read: Any groundwater that may be encountered during excavation and is pumped out must not be pumped down the river bank directly over the ground surface. The groundwater only shall be pumped and carried via a hose from the excavation and discharged directly into the river.
- Add: E12.3(b)(ix): The Contractor shall meet all Provincial regulations when installing depressurization wells and pumping groundwater from the excavation.
- Add: E12.3(b)(x): The Contractor shall be responsible for testing the groundwater from the excavation to applicable guidelines prior to discharge into the river. If the groundwater test results are deemed to be unsuitable for discharge into the river, the Contractor shall be responsible for removing the groundwater from the site by tanker truck and disposing the groundwater at a water treatment plant.