

GENERAL NOTES:

- 1. PERFORM WORK IN ACCORDANCE WITH ALL APPLICABLE CODES AND REGULATIONS.
- 2. REVIEW EQUIPMENT LOCATIONS WITH CONTRACT ADMINISTRATOR PRIOR TO INSTALLATION.
- 3. PIPE ROUTING INDICATED ON DRAWINGS ARE APPROXIMATE ONLY, CONFIRM IN FIELD. REROUTE PIPING TO ELIMINATE FIELD INTERFERENCES WITH BUILDING STRUCTURES, ELECTRICAL ETC. CONFIRM CHANGES WITH CONTRACT ADMINISTRATOR.
- 4. FIRE SEAL ALL PIPE PENETRATIONS TO MAINTAIN EXISTING FIRE SEPARATIONS.
- 5. REFER TO PIPING SCHEMATICS FOR DETAILS.

INDICATED IN STRUCTURAL DRAWINGS.

- 6. PROVIDE ACCESS DOORS FOR ALL EQUIPMENT AND DAMPERS LOCATED ABOVE DRYWALL CEILINGS.
- 7. PIPING TO CABINET UNIT HEATERS CAN BE SURFACE MOUNT. PIPING TO BE PROTECTED USING BENT PLATE SHROUD AS



KEY NOTES:

- INSTALL NEW GLYCOL SUPPLY (GS) AND GLYCOL RETURN (GR) PIPING AS INDICATED. (TYP)
- RUN PIPING DOWN TO REHEAT COILS. REFER TO DRAWING M3 FOR REHEAT COIL LOCATIONS (TYP).
- TIE NEW GLYCOL SUPPLY AND RETURN PIPING INTO GLYCOL SUPPLY AND RETURN PIPING INSTALLED DURING PREVIOUS

LEGEND:

NEW EQUIPMENT OR PIPING

EXISTING EQUIPMENT/DUCTWORK/PIPING

RE-HEAT COIL

GLYCOL SUPPLY

GLYCOL RETURN

CABINET UNIT HEATER

Winnipeg PROJECT TITLE

THE CITY OF WINNIPEG PLANNING, PROPERTY AND DEVELOPMENT DEPARTMENT

FORT ROUGE LEISURE CENTRE HVAC UPGRADE — PHASE 2 BID OPPORTUNITY NO. 190—2013 SECOND/MEZZANINE FLOOR PLAN

NEW PIPING

001 001 COMPUTER FILE NAME 11-0107-02-P2-M04 CITY DRAWING NUMBER

APEGIN Certificate of Authorization KGS Group No. 245

CONSULTING ENGINEERS
& PROJECT MANAGERS WINNIPEG (204) 896-1209 THUNDER BAY (807) 345-2233 **GROUP** CHECKED DRAWN BY APPROVED RE-ISSUED FOR TENDER 12/04/23 PSS HOR. SCALE: AS SHOWN RELEASED FOR RE-ISSUED FOR TENDER CONSTRUCTION: VERTICAL: 12/04/11 PSS ISSUED FOR TENDER DATE NO. REVISIONS

CONSULTANT DRAWING NO. P2-M04