#	DESCRIPTION	RIM ELEV.	BTM ELEV.	LEAD INV.	CONNECTION STATION AND OFFSET	EXISTING SEWER INVERT AT CONNECTION STATION	CB LEAD CONNECTION TYPE
1	CATCH BASIN - NB GUTTER	230.707	228.447	229.047	STA. 0+137.270, 7.550 R NB BASELINE	-	EXIST. LEAD
2	CATCH BASIN - SB GUTTER	230.719	228.459	229.059	STA. 0+184.521, 5.958 R NB BASELINE	227.372	EXIST. 1050 LDS
3	CATCH BASIN - NB GUTTER	230.719	228.459	229.059	STA. 0+185.039, 5.955 R NB BASELINE	227.371	EXIST. 1050 LDS
4	CATCH BASIN - EAST BLVD	230.800	228.540	229.140	STA. 0+211.244, 5.809 R NB BASELINE	227.340	EXIST. MH
5	CATCH PIT - SB GUTTER	230.651	229.751	229.751	-	-	NEW CB
6	CATCH BASIN - SB GUTTER	230.653	228.393	228.993	-	-	EXIST. LEAD
7	CATCH BASIN - SB GUTTER	231.949	229.689	230.289	STA. 0+307.353, 5.894 R NB BASELINE	227.301	EXIST. 1200 LDS
8	CATCH BASIN - WEST BLVD	231.100	228.840	229.440	STA. 0+311.477, 5.898 R NB BASELINE	227.299	EXIST. 1200 LDS
9	CATCH PIT - NB GUTTER	230.591	229.691	229.691	-	-	NEW CB
10	CATCH BASIN - NB GUTTER	230.593	228.333	228.933	STA. 0+253.319, 5.842 R NB BASELINE	227.323	EXIST. 1200 LDS
11	CATCH BASIN - EAST BLVD	230.650	228.390	228.990	STA. 0+256.536, 5.845 R NB BASELINE	227.321	EXIST. 1200 LDS
12	CATCH BASIN - EAST BLVD	230.850	228.590	229.190	STA. 0+271.172, 5.860 R NB BASELINE	227.315	EXIST. 1200 LDS
13	CATCH BASIN - EAST BLVD	230.800	228.540	229.140	STA. 0+330.307, 5.438 R NB BASELINE	227.290	EXIST. MH
14	CATCH BASIN - EAST BLVD	230.400	228.140	228.740	STA. 0+350.423, 24.869 R NB BASELINE	227.209	EXIST. 1200 LDS
15	CATCH BASIN - EAST BLVD	230.400	228.140	228.740	STA. 0+232.316, 27.196 R NB BASELINE	227.199	EXIST. 1200 LDS
16	CATCH BASIN - EAST BLVD	230.800	228.540	229.140	STA. 0+383.208, 11.350 R NB BASELINE	228.060	NEW LDS
17	CATCH BASIN - EAST BLVD	230.800	228.540	229.140	STA. 0+385.623, 11.350 R NB BASELINE	228.022	NEW LDS
18	CATCH PIT - SB GUTTER	230.912	230.012	230.012	-	-	NEW CB
19	CATCH BASIN - SB GUTTER	230.923	228.663	229.263	STA. 0+442.535, 11.386 R NB BASELINE	227.135	NEW LDS
20	CATCH BASIN - NB GUTTER	230.997	228.737	229.337	STA. 0+477.764, 11.350 R NB BASELINE	226.903	NEW LDS
21	CATCH PIT - NB GUTTER	231.009	230.109	230.109	-	-	NEW CB
22	CATCH PIT - SB GUTTER	231.336	230.436	230.436	-	-	NEW CB
23	CATCH PIT - SB GUTTER	231.386	230.486	230.486	-	-	NEW CB
24	CATCH BASIN - NB GUTTER	231.186	228.926	229.526	STA. 0+604.607, 12.605 R NB BASELINE	227.615	NEW LDS
25	CATCH PIT - NB GUTTER	231.422	230.522	230.522	-	-	NEW CB
26	CATCH BASIN - SB LANE	231.406	229.146	229.746	STA. 0+602.979, 12.536 R NB BASELINE	227.607	NEW LDS
27	CATCH BASIN - SB LANE	231.278	229.018	229.618	STA. 0+709.577, 11.650 R NB BASELINE	228.254	NEW LDS
28	CATCH PIT - SB GUTTER	231.208	230.308	230.308	-	-	NEW CB
29	CATCH PIT - SB GUTTER	231.192	230.292	230.292	-	-	NEW CB
30	CATCH PIT - NB GUTTER	231.180	230.280	230.280	-	-	NEW CB
31	CATCH BASIN - NB GUTTER	231.162	228.902	229.502	STA. 0+714.963, 11.650 R NB BASELINE	228.284	NEW LDS
32	CATCH BASIN - WEST BLVD	231.200	228.730	229.330	STA. 0+721.343, 11.650 R NB BASELINE	-	NEW MH
33	CATCH BASIN - WEST BLVD	231.400	229.140	229.740	-	-	NEW CB
34	CATCH BASIN - WEST BLVD	231.150	228.890	229.490	STA. 0+862.979, 19.322 L SB BASELINE	228.280	EXIST. MH
35	CATCH BASIN - EAST BLVD	230.400	228.140	228.740	STA. 0+873.883, 11.975 L SB BASELINE	-	EXIST. CB
36	CATCH PIT - NORTH BLVD	230.680	229.780	229.780	-	-	NEW CB
37	CATCH BASIN - SOUTH BLVD	231.150	228.890	229.490	STA. 0+468.580, 44.672 R NB PANET BASELINE	226.536	NEW LDS
38	CATCH BASIN - WB GUTTER	230.462	228.202	228.802	STA. 2+120.124, 3.727 R WB BASELINE	227.541	EXIST. 525 LDS
39	CATCH BASIN - WB GUTTER	231.235	228.975	229.575	STA. 2+263.405, 2.479 L EB BASELINE	228.161	EXIST. MH
40	CATCH BASIN - SOUTH BLVD	230.800	228.540	229.140	STA. 2+323.373, 13.710 R EB BASELINE	-	NEW MH
41	CATCH BASIN - NORTH BLVD	230.800	228.540	229.140	STA. 2+325.100, 11.434 L WB BASELINE	-	NEW MH
42	CATCH BASIN - EB GUTTER	231.286	229.026	229.626	STA. 0+468.666, 42.405 NB PANET BASELINE	226.575	NEW LDS

APEGM
Certificate of Authorization
Dillon Consulting Limited (MB)
No. 1789 Date: 01/14/2014

EXISTING	LEGEND–PLAN	PROPOSED	EXISTING	LEGEND–PLAN	PROPOSED	EXISTING	LEGEND–PROFILE	PROPOSED
150 WM	WATERMAIN	150 WM	HYDRO	HYDRO	HYDRO	150 WM	WATERMAIN	150 WM
	HYDRANT		MTS	M.T.S.	MTS		HYDRANT	
	VALVE			CONCRETE			VALVE	
300 LDS	LAND DRAINAGE SEWER	300 LDS		ASPHALT		300 LDS	LAND DRAINAGE SEWER	300 LDS
250 WWS	WASTE WATER SEWER	250 WWS		PLANING		250 WWS	WASTE WATER SEWER	250 WWS
	MANHOLE			SIDEWALK			℄ PROFILE	
	CATCH BASIN			PAVING STONES			NORTH/WEST GUTTER	
	CURB INLET			PARTIAL DEPTH REPAIR			SOUTH/EAST GUTTER	
	JUNCTIONS			PROPERTY LINE			NORTH/WEST DITCH	
	CULVERT			DRAINAGE ARROW			SOUTH/EAST DITCH	
100 GAS	GAS	100 GAS		CURB RAMP				

UNDERGROUND STRUCTURES

SUPV. U/G STRUCTURES DATE

LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE, BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

B.M. ELEV.

NO.	REVISIONS	DATE	BY
1	ISSUED FOR ADDENDUM NO. 3	01/14/14	JNC

DESIGNED BY WPN
DRAWN BY TJH
CHECKED BY JNC
APPROVED BY DPK
HOR. SCALE
VERTICAL
DATE 01/14/2014

DILLON CONSULTING

RELEASED FOR CONSTRUCTION
DATE

ENGINEER'S SEAL
PROVINCE OF MANITOBA
ORIGINAL STAMPED BY
W.P. NAIRN
01/14/2014
Member
34277
REGISTERED PROFESSIONAL ENGINEER

CONSULTANT PROJECT NUMBER
12-7055

Winnipeg

THE CITY OF WINNIPEG
PUBLIC WORKS DEPARTMENT

PANET ROAD/MOLSON STREET
RECONSTRUCTION AND TWINNING

CITY DRAWING NUMBER P-3350-47
SHEET 47 OF 47

CATCH BASIN INFORMATION

CONSULTANT DRAWING NUMBER

G:\CAD\127055\02-Civil\01-Contract\25-Catch-Basin-Data.dwg