

## 109-2015 ADDENDUM 1

WPCC Re-Roofing: NEWPCC Dewatering Building and WEWPCC / Perimeter Road PUMPING Station

ISSUED: April 9, 2015  
BY: Matt Klowak, C.E.T.  
TELEPHONE NO. (204) 986-3982

### **URGENT**

**PLEASE FORWARD THIS DOCUMENT TO  
WHOEVER IS IN POSSESSION OF THE BID  
OPPORTUNITY**

**THIS ADDENDUM SHALL BE INCORPORATED  
INTO THE BID OPPORTUNITY AND SHALL  
FORM A PART OF THE CONTRACT  
DOCUMENTS**

Template Version: A20150105

---

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 8 of Form A: Bid may render your Bid non-responsive.

---

### **PART D – SUPPLEMENTAL CONDITIONS**

Revise: D2.2(a) to read: The removal of approximately 1,500 square meters of existing built-up roofing from Area 1, 255 square metres from Area 2 and **290** square metres from Area 3,

Revise: D2.2(e) to read: The supply and installation of approximately 1,500 square meters of both modified bitumen roofing base and cap sheet in Area 1, 255 square metres in Area 2 and **290** square meters in Area 3,

### **PART E – SPECIFICATIONS**

Add: E3.21 Parapets to include a layer of plywood or recovery board on the inside wall and top as deemed necessary for roofing system adhesion by the contractor, and in conjunction with City personnel. Accessible parapet cap joints to be resealed with caulking as determined on-site with City personnel.

### **DRAWINGS**

Replace: 109-2015\_Drawing\_109-2015 with 109-2015 \_Addendum\_1 Drawing 1-0103M-B0001-001\_R1

### **DIVISION 7 – THERMAL AND MOISTURE PROTECTION – MODIFIED BITUMINOUS MEMBRANE ROOFING**

Delete: 1.3

Revise: 2.1.2 to read: Air/Vapour Barrier: **Hot or Cold Applied** air/vapour barrier composed of Styrene-Butadiene-Styrene (SBS) modified bitumen reinforced with high density polyethylene film, anti slip surface, minimum thickness 1.0 mm.

Delete: 2.2.3

Delete: 2.2.4

Revise: 3.3.2.4 to read: Plywood and lumber nailer plates have been installed to deck, walls and parapets as required **for proper roofing system installation.**

Revise: 3.4.1.1 to read: Prime all surfaces to receive modified bituminous sheet air/vapour barrier as per manufacturer's instructions.

Revise: 3.4.1.2 to read: Apply modified bituminous sheet air/vapour barrier to concrete deck or deck substrate in an overlapping shingle fashion and as per manufacturer's specifications. Stagger all vertical joints.

Delete: 3.4.1.3

Delete: 3.4.3

Delete: 3.4.4