

# SPECIFICATIONS

## 099000 PAINTING

### Part 1 General

#### 1.1 REFERENCES

SPEC NOTE: Edit list of standards to include only those standards referenced in project specification.

- .1 American Society for Testing and Materials International, (ASTM).
  - .1 ASTM D610\_[01], Test Method for Evaluating Degree of Rusting on Painted Steel Surfaces.
  - .2 ASTM D2369\_[03], Test Method for Volatile Content of Coatings.
  - .3 ASTM D2832\_[92(R1999)], Guide for Determining Volatile and Nonvolatile Content of Paint and Related Coatings.
  - .4 ASTM D5326\_[94a(2002)], MPI-9 Test Method for Color Development in Tinted Latex Paints.
- .2 Environmental Choice Program (ECP).
  - .1 CCD-048-[95], Recycled Water\_borne Surface Coatings.
  - .2 CCD-047a-[98], Paints - Surface Coatings.
  - .3 Federal Standard (FS).
    - .1 FS\_595B\_[89], Paint Colours.

### Part 2 Products

#### 2.1 MATERIALS

- .1 Acceptable paint manufactures
  - .1 Glidden Professional
  - .2 PPG Architectural Finishes, Inc.
  - .3 Sherwin Williams Benjamin Moore & Co.
- .2 Source Limitations: Obtain paint materials from single source from single listed manufacturer.

#### 2.2 PAINT

- .1 Structural Steel and Metal Fabrications:
  - .1 EXT 5.1C Water based light industrial G5 coating over alkyd primer. Colour to be determined by City of Winnipeg Project Manager

### Part 3 Execution


- .1 Compliance: comply with manufacturer's written data, including product technical bulletins, product catalogue installation instructions, product carton installation instructions, and data sheets.
- .2 Complete work in accordance with Master Painters Institute Specifications and approved procedures.

END OF SECTION

  
John van Leeuwen  
Architecture and Design  
211-63 Albert Street Wpg., Mb R3B 1G4  
Ph: 204-504-7443

CITY OF WINNIPEG  
CENTRAL FREIGHT HOUSE  
WHEELCHAIR RAMP AND STAIR  
RETROFIT - DOOR 6  
WINNIPEG, MANITOBA

CLIENT REVIEW SIGNATURE:



ARCHITECTURAL SEAL

SHEET TITLE:  
SPECIFICATION

PROJECT NO: 2014052  
DRAWN BY: RR  
CHECKED BY: JV  
SCALE:  
ISSUED FOR: REVIEW  
ISSUE DATE: APRIL 8, 2015

**AA-003(6)**

SD  
DATE PLOTTED  
4/8/15