



**PRECAST CONCRETE BEAM SCHEDULE**  
 P/C-B3 18" X 21" (INVERTED TEE)  
 P/C-B30 18" X 21" (L BEAM)

**MEZZANINE FLOOR LOADING**  
 SUPERIMPOSED LIVE LOAD = 75 P.S.F.  
 SUPERIMPOSED DEAD LOAD = 25 PSF

**PRECAST CONCRETE COLUMN SCHEDULE**  
 P/C-COL-1 16" X 16"  
 P/C-COL-2 24" X 24"

**NOTE:**  
 PRECAST CONCRETE SUPPLIER RESPONSIBLE FOR ENSURING STRUCTURAL STABILITY /210 WIND DIAPHRAM DESIGN (RESISTANCE)

SWIM MANITOBA  
 PAN AM POOL ADDITION

**ARC + CADD**

JOB # 93009  
 DATE JUN 1, 1993  
 DRAWN BY U.S.  
 CHECK BY J.S.H.



SHEET TITLE  
**MEZZANINE FRAMING PLAN**

SCALE 1/8"=1'-0"  
 CAD FILE PAN223-2

GENERAL REVISION  
 DATE JULY 28/93