

APPENDIX B (R1) – WATERMAIN RENEWAL LOCATIONS

TABLE A

STREET NAME	LOCATION DETAILS	DIAM. (mm)	LENGTH (M)
PRINCESS ST	HIGGINS AV TO JAMES AV	300	980
WATERMAIN ABANDONMENT- PRINCESS ST	VARIOUS	varies	varies
TOTAL BUDGET	\$1,905,461		

TABLE B

PLEASE NOTE: The locations and quantities of the abandonments detailed in Appendix B are based upon a preliminary review by Water and Waste staff. The abandonment of hydrants, valves and interconnections should not be limited to these quantities/locations and could vary once a more detailed review is performed by the Consultant.

LOCATION	ACTION REQUIRED
Princess Street @ Higgins Avenue	<ul style="list-style-type: none"> Cut and Plug 300 CI WM
Princess Street @ Henry Avenue	<ul style="list-style-type: none"> Abandon 250mm Valve. Abandon Hydrant and Valve. Remove interconnect between two mains at King Street (cut out 200mm Tee and pipe through
Princess Street @ Logan Avenue	<ul style="list-style-type: none"> Abandon Hydrant and Valve. Abandon 300mm Valve
Princess Street @ Alexander Avenue	<ul style="list-style-type: none"> Connect 250 CI East of Princess to 300 CI West of Princess
Princess Street @ Pacific Avenue	<ul style="list-style-type: none"> Abandon 300mm Valve.
Princess Street @ Rupert Avenue	<ul style="list-style-type: none"> Abandon Hydrant and Valve.
Princess Street @ James Avenue	<ul style="list-style-type: none"> Abandon 2- 300mm Valve. Connect 250 CI WM into 300 CI WM on South side of James Avenue
Princess Street @ South of Elgin Avenue	<ul style="list-style-type: none"> Abandon 300mm Valve
Princess Street @ William Avenue	<ul style="list-style-type: none"> Abandon 300mm Valve