



ROOF DRAIN SCHEDULE - CONTROL FLOW											
	DRAINAGE AREA						WATER STORAGE		SCUPPERS		
ROOF TAG	ROOF	LARGEST WALL	TOTAL	NUMBER OF DRAINS	TOTAL NUMBER OF WEIRS	FLOW	MAX DEPTH	DRAIN DOWN TIME	DESIGN HEAD	MIN TOTAL WIDTH	SCUPPER LOAD
1	7929 SF	0 SF	7929 SF	3	3	72 GPM	0' - 6"	20 minutes	0' - 1"	20' - 3"	660 GPM

1. BOTTOM OF SCUPPER SHALL BE EXACTLY 5" (125mm) ABOVE LEVEL OF ROOF DRAIN. 2. SCUPPERS SHALL BE INSTALLED EVERY 100' (30m) ALONG THE PERIMETER OF ALL ROOFS.

Certificate of Authorization Epp Siepman Engineering Inc. No. 4035



GENERAL NOTES

- A. SITE PLAN INDICATES LOCATIONS OF PLUMBING, SPRINKLER, HYDRONIC AND HVAC EQUIPMENT AND SERVICES. CONTRACTOR SHALL COORDINATE LOCATIONS AND REQUIREMENTS WITH SUB-TRADES.
 B. REFER TO ARCHITECTURAL PLANS, ELEVATIONS AND ROOF PLANS FOR ADDITIONAL INFORMATION ON INSTALLATION HEIGHTS, EXACT LOCATIONS, AND SUPPORTING INFORMATION.
 C. REFER TO CIVIL AND STRUCTURAL PLANS FOR LOCATIONS OF SITE SERVICES, STRUCTURAL RESTRICTIONS AND COORDINATE BETWEEN TRADES.

KEY NOTES

- LOCATION OF NATURAL GAS METER. 1 BUILDING VENT.
- 2 WALL HYDRANT LOCATION 3



epp siepman engineering inc. mechanical & electrical engineers 303-100 Osborne St. South Winnipeg, MB

Winnipeg, MB R3L 1Y5	p 204.453.1080 ese@eppsiepman.com
O 16-03-31 revision	Issued for Construction
ARCHITECTURE AND D MAY NOT BE REPRO MANNER WITHOUT PERMISSION. THE G MATERIALS SUPPLIER: AND INFORMATION ON	E EXCLUSIVE PROPERTY OF H5 DAVID PENNER ARCHITECT AND DUCED AND/OR USED IN ANY THEIR EXPRESSED WRITTEN & ENERAL CONTRACTOR AND S SHALL CHECK ALL DIMENSIONS THIS DRAWING AND REPORT ANY & TO COMMENCEMENT OF WORK. AWING.
OWNER	
	Winnipeg
CITY OF WINNIPEG	- PLANNING, PROPERTY



As indicated



site plan M1.1