

1. GENERAL

1.1. RELATED REQUIREMENTS

- .1 Section 12 36 61.16 Solid Surfacing Countertops

1.2. DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Deliver appliances only when the project is ready for installation and the contractor has provided a clean storage area.
- .3 Store and protect appliances and accessories from nicks, scratches, and blemishes.

2. PRODUCTS

2.1. MATERIALS

- .1 Staff room: City supplied refrigerator and microwave.

3. EXECUTION

3.1. INSTALLATION

- .1 Install appliances in accordance with manufacturer's instructions and approved submittals. Install materials and systems in proper relation with adjacent construction and with uniform appearance. Coordinate with work of other sections.
- .2 Restore damaged finishes and test for proper operation. Clean and protect work from damage.

END OF SECTION.

1. GENERAL

1.1 RELATED REQUIREMENTS

- .1 Section 03 30 00 – Cast-in-Place Concrete
- .2 Division 26 for electrical requirements

1.2 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with Section 01 61 00 - Common Product Requirements and with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site in original factory packaging, labelled with manufacturer's name and address after building is enclosed.
- .3 Storage and Handling Requirements:
 - .1 Store materials off ground indoors in dry location and in accordance with manufacturer's recommendations in clean, dry, well-ventilated area.
 - .2 Protect screen from damage during delivery, handling, storage and installation.
- .4 Packaging Waste Management: remove for reuse and return of pallets, crates, padding, and packaging materials.

2. PRODUCTS

2.1 MANUFACTURED UNITS

- .1 Manufacturer: Draper, Inc.
 - .1 Silhouette Series E, fiberglass matt white screen
 - .1 6' x 8' AV format, wall mounted, case finish white, motorized c/w 3-position rocker switch
 - .2 Provide wall mounting bracket free of exposed fasteners.

3. EXECUTION

3.1 EXAMINATION

- .1 Coordination of Work: coordinate electrical work within c.i.p. concrete wall and confirm location with Contract Administrator.
- .2 Verification of Conditions: verify that conditions of substrates and surfaces to receive projection screen previously installed under other Sections or Contracts are acceptable for product installation in accordance with manufacturer's instructions.
- .3 Inform Contract Administrator of unacceptable conditions immediately upon discovery.
- .4 Proceed with installation only after unacceptable conditions have been remedied and after receipt of written approval from Contract Administrator.

3.2 INSTALLATION

- .1 Install front projection screens with screen cases in position and relationship to adjoining construction as indicated, securely anchored to supporting substrate, and in manner that produces a smoothly operating screen with plumb and straight vertical edges and plumb and flat viewing surfaces when screen is lowered.

3.3 PROTECTION

- .1 Protect installed products and components from damage during construction.
- .2 Repair damage to adjacent materials caused by installation.

END OF SECTION.