



ROOF DRAINS SCHEDULE

MAIN DATA	RD-1,3	RD-2	RD-4
AREA PER DRAIN, sq.ft.	9200	9000	3550
TOTAL ROOF SLOPE, in.	4	4	4
DRAIN SIZE, in.	3	3	2
AMOUNT OF NOTCHES	2	2	1
FLOW PER NOTCH, gpm	18.8	18.7	17.5
DRAIN DOWN TIME, hrs	8.7	8.8	6.0
WATER DEPTH, in	3.8	3.7	3.5

SWIM MANITOBA
PAN AM POOL ADDITION

SEG SEG ENGINEERING INC.
200 BAY STREET, WINNIPEG, MANITOBA, CANADA R2S 1K8
(204) 253-2113

FARACI ENGINEERING LTD.
800 FINE STREET, WINNIPEG, MANITOBA, CANADA R2S 1K8

JOB # 83071
DATE JULY 24, 1983
DRAWN BY M.L.
CHKD BY E.A.F.

SHEET TITLE
ROOF PLAN
MECHANICAL

SCALE 1/8" = 1'-0" SHIT No. M-4.1
CAD FILE ABL7M4

AS BUILT

MECH.