



NOTES

- 1 CONFIRM OPENING LOCATIONS BASED ON SITE CONDITIONS/INVESTIGATIONS
- 2 WOOD FRAMING TO CAN/CSA-086.1 & D86S1-05
- 3 WOOD FRAMING MATERIALS NO. 2 GRADE OR BETTER
- 4 PREPARE MOCK UP OF INITIAL OPENING FOR ENGINEERS REVIEW TO ESTABLISH STD. OF ACCEPTANCE FOR ALL OPENINGS
- 5 FLASH AND CAULK ALL FRAMED OPENINGS TO BE WATERTIGHT; TAPE AND SECURE VB TO NEW ROUGH OPENING VB AND MAINTAIN VAPOUR BARRIER INTEGRITY
- 6 RESTORE ANY AFFECTED SURFACES TO AS NEW CONDITION AND TO MATCH EXISTING
- 7 FAN ROUGH OPENINGS TO UTILIZE SIMILAR FRAMING DETAILS



THE CITY OF WINNIPEG
 WATER AND WASTE DEPARTMENT



Alliance
 ENGINEERING SERVICES INC.

HVAC SYSTEM
 WALL PENETRATION DETAIL

| | | |
|-----------------------|--------------------|------------------|
| ISSUED FOR ADDENDUM 2 | DATE 2016/07/27 | DWG. NO. SK-1 |
|-----------------------|--------------------|------------------|