

ROOM FINISH SCHEDULE - ST. VITAL LIBRARY

ROOM NUMBER	ROOM NAME	AREA	NORTH WALL	N. FINISH	EAST WALL	E. FINISH	SOUTH WALL	S. FINISH	WEST WALL	W. FINISH	FLOOR FINISH	BASE MATERIAL	CEILING MATERIAL	CEILING HEIGHT	CEILING FINISH	COMMENTS
101	CHILDREN'S & ADULTS BOOKS	1003 SF	EXIST GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	CPT	RWB	EXIST ACOUSTIC PLASTER	+/- 8'-0"	PTD	
102	PUBLIC SPACE	1105 SF	EXIST GWB	PTD	EXIST GWB	PTD	PLWD PANEL	CLR SEAL	EXIST GWB	PTD	CPT & SVF	RWB/ALUM	EXIST WOOD DECK	VARIES	EXIST	
103	VESTIBULE	117 SF	PLWD PANEL/GWB	CLR SEAL/PTD	PLWD PANEL/GWB	CLR SEAL/PTD	PLWD PANEL/GWB	CLR SEAL/PTD	PLWD PANEL/GWB	CLR SEAL/PTD	SVF	ALUM	GWB	9'-0"	PTD	REMOVE EXISTING WD CEILING FINISH, NEW GYPSUM BOARD CEILING TO BE INSTALLED OVER EXIST PLWD SUBSTRATE.
104	UTR	116 SF	WATER-RESISTANT GWB	EPOXY PTD	MOISTURE RESISTANT GWB	EPOXY PTD	MOISTURE RESISTANT GWB	EPOXY PTD	MOISTURE RESISTANT GWB	EPOXY PTD	SVF	COVE	MOISTURE RESISTANT GWB	8'-0"	EPOXY PTD	REFER TO INTERIOR ELEVATIONS FOR SOLID SURFACE BACKSPLASH LOCATIONS.
105	CHILDREN'S AREA	413 SF	EXIST GWB	PTD	EXIST GLAZING FRAMES	PTD	EXIST GLAZING FRAMES	PTD	EXIST GWB	PTD	CPT	RWB	EXIST WOOD DECK	+/- 12'-0"	EXIST	EXISTING WINDOW FRAMES AND BASE INFILL PANELS TO BE PAINTED.
108	SERVICE ENTRANCE	42 SF	EXIST GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	SVF	RWB	EXIST CONC	+/- 9'-0"	EXIST	
109	WORK ROOM	288 SF	EXIST GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	SVF	RWB	EXIST ACT/ACT	+/- 8'-8"	EXIST	REFER TO RCP FOR EXTENT OF NEW ACT, NEW CLG HEIGHT TO MATCH EXISTING ADJACENT CEILING.
110	STAFF LUNCH ROOM	234 SF	EXIST GWB/GWB	EPOXY PTD	GWB	EPOXY PTD/PTD	EXIST GWB	PTD	EXIST GWB	OXY PTD/PTD	SVF	COVE	ACT	+/- 8'-8"	--	NEW CEILING HEIGHT TO MATCH EXISTING CEILING HEIGHT OF WORKROOM.
111	W/C	37 SF	MOISTURE RESISTANT GWB	EPOXY PTD	MOISTURE RESISTANT GWB	EPOXY PTD	MOISTURE RESISTANT GWB	EPOXY PTD	MOISTURE RESISTANT GWB	EPOXY PTD	SVF	COVE	MOISTURE RESISTANT GWB	+/- 8'-8"	EPOXY PTD	REFER TO INTERIOR ELEVATIONS FOR SOLID SURFACE BACKSPLASH LOCATIONS. NEW CEILING HEIGHT TO MATCH EXISTING CEILING HEIGHT OF WORKROOM (RM 109).
112	LIBRARIANS OFFICE	127 SF	GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	GWB	PTD	CPT	RWB	ACT	+/- 8'-8"	--	NEW CEILING HEIGHT TO MATCH EXISTING CEILING HEIGHT OF WORKROOM (RM 109).
114	STACKS	2369 SF	EXIST GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	CPT	RWB	EXIST WOOD DECK	+/- 11'-11"	EXIST	
115	STAIR	111 SF	EXIST GWB	EXIST	EXIST GWB	EXIST	EXIST GWB	EXIST	EXIST GWB	EXIST	EXIST	--	EXIST CONC	VARIES	EXIST	
116	STAIR 2	55 SF	--	--	--	--	PLWD PANEL	CLR SEAL	--	--	CPT	--	--	--	--	STAIR TO HAVE CARPET TREADS & RISERS C/W COLOUR CONTRASTING NOSING & TACTILE FLOORING AREAS AS INDICATED.
117	STAIR 1	75 SF	EXIST GWB	PTD	EXIST GWB	PTD	--	--	EXIST GWB	PTD	CPT	--	--	--	--	STAIR TO HAVE CARPET TREADS & RISERS C/W COLOUR CONTRASTING NOSING & TACTILE FLOORING AREAS AS INDICATED.
201	MEZZANINE ONE - LOUNGE	714 SF	EXIST GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	CPT	RWB	EXIST WOOD DECK	+/- 9'-2"	EXIST	
202	MEZZANINE TWO - YOUNG ADULTS	930 SF	EXIST GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	CPT	RWB	EXIST WOOD DECK	VARIES	EXIST	
203	ELEVATOR ROOM	70 SF	EXIST GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	CPT	RWB	EXIST GWB	+/- 9'-6"	EXIST	
B-01	EXHIBIT SPACE	960 SF	EXIST GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	CPT	RWB	EXIST ACT	+/- 7'-8"	EXIST	
B-02	EXHIBIT SPACE	859 SF	EXIST GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	CPT	RWB	EXIST ACT/GWB	+/- 7'-11"	EXIST	REFER TO RCP FOR EXTENT OF NEW GWB CEILING/BULKHEAD.
B-03	CLOSET	36 SF	EXIST CMU	EXIST	EXIST CMU	EXIST	EXIST CMU	EXIST	EXIST CMU	EXIST	EXIST	EXIST	EXIST ACOUSTIC PLASTER	VARIES	EXIST	
B-04	STAIR	53 SF	EXIST CMU	PTD	EXIST CMU	PTD	EXIST CMU	PTD	EXIST CMU	PTD	RUBBER	--	EXIST ACOUSTIC PLASTER	VARIES	PTD	STAIRS TO RECEIVE NEW RUBBER TREADS C/W CONTRASTING NOSING & TACTILE FLOORING AREAS AS INDICATED.
B-05	UTR	123 SF	EXIST GWB	PTD	MOISTURE RESISTANT GWB	EPOXY PTD	EXIST GWB	PTD	EXIST GWB	PTD	SVF	COVE	MOISTURE RESISTANT GWB	8'-0"	EPOXY PTD	REFER TO INTERIOR ELEVATIONS FOR SOLID SURFACE BACKSPLASH LOCATIONS
B-05A	CLOSET	21 SF	EXIST GWB	PTD	GWB	PTD	GWB	PTD	EXIST GWB	PTD	EXIST CONC	RWB	GWB	8'-0"	PTD	
B-06	MEN'S W/C	33 SF	EXIST GWB/EXIST WALL TILE	EPOXY PTD (GWB)	EXIST GWB/EXIST WALL TILE	EPOXY PTD (GWB)	EXIST GWB/EXIST WALL TILE	EPOXY PTD (GWB)	EXIST GWB/EXIST WALL TILE	EPOXY PTD (GWB)	EXIST	EXIST	EXIST GWB	+/- 8'-0"	EPOXY PTD	
B-07	WOMEN'S W/C	36 SF	EXIST GWB/EXIST WALL TILE	EPOXY PTD (GWB)	EXIST GWB/EXIST WALL TILE	EPOXY PTD (GWB)	EXIST GWB/EXIST WALL TILE	EPOXY PTD (GWB)	EXIST GWB/EXIST WALL TILE	EPOXY PTD (GWB)	EXIST	EXIST	EXIST GWB	+/- 8'-0"	EPOXY PTD	
B-08	JANITOR'S CLOSET	61 SF	EXIST	PTD	EXIST	PTD	EXIST	PTD	EXIST	PTD	SVF	COVE	EXIST	+/- 8'-0"	EXIST	
B-11	TUTORIAL	337 SF	EXIST GWB	PTD	EXIST GWB	PTD	EXIST GWB	PTD	GWB	PTD	CPT	RWB	EXIST ACT/GWB	+/- 7'-11"	EXIST	REFER TO RCP FOR EXTENT OF NEW GWB CEILING/BULKHEAD.
B-12	STORAGE	113 SF	EXIST CMU	PTD	EXIST CMU	PTD	EXIST CMU	PTD	EXIST CMU	PTD	EXIST	EXIST	EXIST ACT	+/- 8'-0"	EXIST	
B-13	ELECTRICAL ROOM	92 SF	EXIST CMU	EXIST	EXIST CMU	EXIST	EXIST CMU	EXIST	EXIST CMU	EXIST	EXIST CONC	EXIST	EXIST ACOUSTIC PLASTER	+/- 8'-0"	EXIST	
B-14	STAIR	44 SF	EXIST CMU	PTD	EXIST CMU	PTD	EXIST CMU	PTD	EXIST CMU	PTD	RUBBER	--	EXIST	VARIES	PTD	STAIRS TO RECEIVE NEW RUBBER TREADS C/W CONTRASTING NOSING & TACTILE FLOORING AREAS AS INDICATED.
B-15A	BOILER ROOM	85 SF	EXIST CMU	EXIST	EXIST CMU	EXIST	EXIST CMU	EXIST	EXIST CMU	EXIST	EXIST CONC	EXIST	EXIST CONC	+/- 9'-7"	EXIST	
B-15B	BOILER ROOM	107 SF	EXIST CMU	EXIST	EXIST CMU	EXIST	EXIST CMU	EXIST	EXIST CMU	EXIST	EXIST CONC	EXIST	EXIST CONC	+/- 9'-7"	EXIST	
B-16	STORAGE	22 SF	EXIST CMU	EXIST	EXIST CMU	EXIST	EXIST CMU	EXIST	EXIST CMU	EXIST	EXIST CONC	CONC	EXIST CONC	VARIES	EXIST	
B-17	STORAGE AREA	2494 SF	EXIST CONC	EXIST	EXIST CONC	EXIST	EXIST CONC	EXIST	EXIST CONC	EXIST	EXIST CONC	EXIST	EXIST CONC	+/- 9'-7"	EXIST	
B-17A	CONTROL CLOSET	21 SF	EXIST	EXIST	EXIST	EXIST	EXIST	EXIST	EXIST	EXIST	EXIST CONC	EXIST	EXIST	+/- 9'-7"	EXIST	
B-18	STAIR	111 SF	EXIST CMU	EXIST	EXIST CMU	EXIST	EXIST CMU	EXIST	EXIST CMU	EXIST	EXIST	--	EXIST CONC	VARIES	EXIST	
B-19	ELEVATOR ROOM	244 SF	EXIST GWB	EXIST	EXIST CONC	EXIST	EXIST GWB	EXIST	EXIST GWB	EXIST	EXIST CONC	EXIST	EXIST CONC	+/- 9'-9"	EXIST	
B-20	W/C	73 SF	MOISTURE RESISTANT GWB	EPOXY PTD	MOISTURE RESISTANT GWB	EPOXY PTD	MOISTURE RESISTANT GWB	EPOXY PTD	MOISTURE RESISTANT GWB	EPOXY PTD	SVF	COVE	MOISTURE RESISTANT GWB	8'-0"	EPOXY PTD	REFER TO INTERIOR ELEVATIONS FOR SOLID SURFACE BACKSPLASH LOCATIONS
B-21	W/C	72 SF	MOISTURE RESISTANT GWB	EPOXY PTD	MOISTURE RESISTANT GWB	EPOXY PTD	MOISTURE RESISTANT GWB	EPOXY PTD	MOISTURE RESISTANT GWB	EPOXY PTD	SVF	COVE	MOISTURE RESISTANT GWB	8'-0"	EPOXY PTD	REFER TO INTERIOR ELEVATIONS FOR SOLID SURFACE BACKSPLASH LOCATIONS

bridgmancollaborative
 ARCHITECTURE
 www.bridgmancollaborative.ca
 678 MAIN STREET WINNIPEG, MB R3B 1E4
 204 488 3857 tel. 204 488 0216 fax.

Winnipeg
 THE CITY OF WINNIPEG PLANNING, PROPERTY AND DEVELOPMENT DEPARTMENT
 MUNICIPAL ACCOMMODATIONS DIVISION
 4TH FLOOR - 185 KING STREET
 R3B 1J1

Project:
St. Vital Library

6 Fermor Ave. Winnipeg, MB
 Project Number: 1605
 Bid Opportunity Number: 788-2016

Drawing Title:
ROOM SCHEDULE

#	Issue/Revision	Date
1	ISSUED FOR CONSTRUCTION	SEPT 9, 2016

Sheet No: **A902**

This drawing is property of the Architect and cannot be reproduced or used without the consent of the Architect. The contractor is responsible for checking and verifying all levels and dimensions and shall report all discrepancies to the Architect and obtain clarification prior to commencing work.