



1 MAIN FLOOR NEW PLUMBING LAYOUT
3/16" = 1'-0"

PLUMBING FIXTURE ROUGH IN				
PLUMBING FIXTURE	DCW	DHW	SAN	VENT
WATER CLOSET (FT)	½"Ø	-	4"Ø	2"Ø
LAVATORY	½"Ø	½"Ø	1 ½"Ø	1 ½"Ø
KITCHEN SINK	½"Ø	½"Ø	1 ½"Ø	1 ½"Ø
MOP SINK	½"Ø	½"Ø	2"Ø	1 ½"Ø

DRAWING KEYNOTES:

1. NEW 2" VENT STACK, CUT AND PATCH AS REQUIRED.
2. EXISTING 2" VENT STACK TO REMAIN.

GENERAL NOTES:

1. DO NOT SCALE THIS DRAWING. CONTRACTOR SHALL VERIFY ALL DIMENSIONS PRIOR TO INSTALLATION AND REPORT ANY DISCREPANCY TO THE CONTRACT ADMINISTRATOR.
2. THE DRAWING ONLY SHOWS A GENERAL SCHEMATIC OF NEW SYSTEMS. ROUTING OF PIPING AND UNITS LOCATIONS SHALL SUIT SITE CONDITIONS AND MAY HAVE TO BE CHANGED TO AVOID CONFLICTS WITH STRUCTURE, DUCTS AND PIPES. WHEN CONFLICT CANNOT BE AVOIDED, THE DUCTWORK SHALL BE MODIFIED AS REQUIRED.
3. CONTRACTOR SHALL INCLUDE FOR AND PROVIDE ALL COORDINATION BETWEEN TRADES AND CONSULTANT ON AND OFF SITE AS REQUIRED FOR INSTALLATION OF MECHANICAL AND ELECTRICAL SYSTEMS. WHERE MINOR REROUTING OF DUCT OR SERVICES IS REQUIRED DUE TO ON-SITE CONDITIONS, IT SHALL BE PERFORMED AT NO ADDITIONAL COST.
4. CRAWLS SPACE IS A CONFINED AREA. CONTRACTOR TO CONFIRM ALL EXISTING PLUMBING PIPING IN CRAWL SPACE AND MAKE CONNECTIONS AS REQUIRED.
5. COORDINATE ALL PIPING ROUTING WITH ARCHITECTURAL ELEMENTS. ALLOW FOR CUTTING AND PATCHING WHERE EXISTING WALLS, CEILINGS AND ARCHITECTURAL FEATURES ARE REQUIRED TO BE OPENED FOR PIPING.



THE CITY OF WINNIPEG PLANNING,
PROPERTY AND DEVELOPMENT
DEPARTMENT
MUNICIPAL ACCOMMODATIONS DIVISION
4TH FLOOR - 185 KING STREET
R3B 1J1

Project:
St. Vital Library

6 Fermor Ave., Winnipeg, Manitoba

Project Number: 10004
S&I Opportunity Number: 7165-2016

Drawing Title:
MAIN FLOOR NEW
PLUMBING LAYOUT

Issue/Revision Date
1 ISSUED FOR CONSTRUCTION SEPT 09, 2016

Sheet No: M-5

This drawing is property of the Architect and cannot be reproduced or used without the consent of the Architect. The contractor is responsible for checking and verifying all levels and dimensions and shall report all discrepancies to the Architect and obtain clarification prior to commencing work.