


KEY PLAN



CONSTRUCTION NOTES:

- 1. CONTRACTOR TO MAINTAIN PUBLIC ACCESS TO R.A. STEEN COMMUNITY CENTRE AT ALL TIMES DURING CONSTRUCTION.
- 2. RESTORE ALL DISTURBED GRASS AREAS WITH IMPORTED TOP SOIL AND SOD IN ACCORDANCE WITH CW 3510.
- 3. LEAVE SLUICE GATE IN EXISTING CHAMBER IN FULL OPEN POSITION AT ALL TIMES EXCEPT WHEN ON SITE WORKING ON GATE.
- 4. PROVIDE TEMPORARY PUMPING OF FLOW IN SRS AS REQUIRED DURING CONSTRUCTION.
- 5. PREVENT EXCAVATED MATERIAL, BACKFILL MATERIAL AND SOIL / WATER SLURRY FROM ENTERING THE SRS OUTFALL TO THE RIVER.
- 6. DO NOT REMOVE EXISTING TREES UNLESS NOTED OTHERWISE. PROVIDE TREE PROTECTION IN
- ACCORDANCE WITH SPECIFICATIONS.
- 7. CONFIRM LOCATION AND ELEVATION OF EXISTING SRS, SEWER MAIN AND WATER MAIN BEFORE CONSTRUCTION COMMENCES.



14/09/2016

THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT Winnipeg

OUTFALL GATE CHAMBER UPGRADES **RUBY STREET** SRS OUTFALL GATE CHAMBER

	consultant drawing number 5516047 - C01		
	SHEET	OF	
		2	34
	CITY DRAWING NUMBER		

These design documents are prepared solely for the use by the party with whom the design professional has entered into a contract and there are no representations of any kind made by the design professional to any party with whom the design professional has not entered into a contract.

MMM Group Limited

No. 4531

(32.50)ELEVATION BB/MRI EΗ GATE VALVE APPROVED KD JPL \bigcirc LIGHT STANDARD MANHOLE AS NOTED RELEASED FOR __ · __ · __ PROPERTY LINE AS NOTED CONSTRUCTION BID OPPORTUNITY: **789-2016** VERTICAL WOOD FENCE ISSUED FOR TENDER 13/09/16 BB DATE BY DATE 13/09/2016 **EXISTING** DESCRIPTION PROPOSED NO. REVISIONS PLOT DATE:

SITE PLAN