

Part 1 General

1.1 REFERENCES

- .1 The General Conditions for Construction (Rev. 2006 12 15) are applicable to the Work of the Contract.
- .2 Canadian Standards Association (CSA International)
 - .1 CSA A23.1/A23.2-09, Concrete Materials and Methods of Concrete Construction/Methods of Test and Standard Practices for Concrete.
 - .2 CSA O121-08, Douglas Fir Plywood.

1.2 SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 - Submittal Procedures.

1.3 SCAFFOLDING

- .1 Provide and maintain scaffolding, swingstage(s), access lift(s) as required for access throughout duration of the Work.
- .2 Scaffolding shall be design and erected in accordance with Manitoba Regulation 217/2006 and CAN/CSA S269.2.
 - .1 Where Manitoba Regulation 217/2006 requires scaffolds to be designed by a professional engineer. Submit shop drawings bearing the seal of professional engineer registered in the Province of Manitoba.

1.4 SUSPENDED ELEVATING PLATFORMS (SWINGSTAGE)

- .1 Swingstage access shall be in accordance with Manitoba Regulation 217/2006, CAN/CSA Z271, and CAN/CSA Z91.
 - .1 Contractor to notify Manitoba Workplace Safety and Health at least 24 hours prior to rigging swingstage(s).
 - .1 Submit proof of notification to the Contract Administrator.
 - .2 Submit a Manitoba Workplace Safety and Health serial number prior to swingstage set-up.
 - .2 Upon request, make available to the Contract Administrator, all pertinent information regarding the swingstage equipment, design, and setup including but not limited to the following:
 - .1 Swingstage platform manufacturer's technical data indicating allowable load capacities;
 - .2 Outrigger manufacturer's or supplier's table of counterweights and allowable projections beyond the fulcrum point for various loads;
 - .3 Outboard thrust, inboard thrust, number and configuration of outrigger counterweights.
 - .4 The purpose of the review is to determine that the swingstage(s) utilized for access and work purposes is in general conformance with the contract documents and does not constitute approval of the swingstage(s) to be used by the Contractor, who shall remain solely responsible for the design, erection, operation, maintenance of the

swingstage(s) and for any errors and omissions of those forces which come under his control.

- .2 Suspended elevating platforms or aerial device shall be designed, and constructed, installed, maintained, used and dismantled, in accordance with Manitoba Regulation 217/2006.

1.5 SITE STORAGE/LOADING

- .1 Confine work and operations of employees by Contract Documents. Do not unreasonably encumber premises with products.
- .2 Do not load or permit to load any part of Work with weight or force that will endanger Work.

1.6 CONSTRUCTION PARKING

- .1 Parking will be permitted on site provided it does not interfere with normal operations, access by tenants or the public, or disrupt performance of Work.

1.7 EQUIPMENT, TOOL AND MATERIALS STORAGE

- .1 Provide and maintain, in clean and orderly condition, lockable weatherproof sheds for storage of tools, equipment and materials.
- .2 Locate materials not required to be stored in weatherproof sheds on site in manner to cause least interference with work activities.

1.8 SANITARY FACILITIES

- .1 Provide sanitary facilities for work force in accordance with governing regulations and ordinances.
- .2 Post notices and take precautions as required by local health authorities. Keep area and premises in sanitary condition.
- .3 The Contractor may at the discretion of the City of Winnipeg, use on-site facilities for the duration of the project. The facilities must be maintained in a neat condition or use will be revoked.

1.9 CLEAN-UP

- .1 Remove construction debris, waste materials, packaging material from work site daily.
- .2 Clean dirt or mud tracked onto paved or surfaced roadways.
- .3 Store materials resulting from demolition activities that are salvageable.
- .4 Stack stored new or salvaged material not in construction facilities.

Part 2 Products

2.1 NOT USED

- .1 Not Used.

Part 3 Execution

3.1 NOT USED

.1 Not Used.

END OF SECTION