



Supply and Install 2-bay swing set

Supply and Install new 2 tier			
timber edging c/w composite			
cap (78 LM)			

Supply and Install engineered wood fibre safety surfacing (273 SM)

Supply and Instal new 2-5 play equipment

General Notes

1.	TOP OF TIMBERS SHALL BE 300MM (12") ABOVE
	EXISTING GRADE AT ITS HIGHEST POINT ON
	THE GROUND
~	

2. EXCAVATION OF PLAY AREA BASED ON APPROX. 150mm DEPTH

3.	FOR RAISED GRANULAR SEATING AREAS REMOVE
	ALL EXISTING ORGANIC MATERIAL TO AN APPROX.
	DEPTH OF 75mm. TOTAL DEPTH OF GRANULAR
	TO BE 375mm
	- REFER TO SCD 646 FOR REFERENCE.

- MATERIAL BREAKDOWN SHALL BE AS FOLLOWS: 200mm OF 2" DOWN CRUSHED LIMESTONE, FOLLOWED BY 150mm OF 3/4" DOWN CRUSHED LIMESTONE, WITH A 25mm TOP COAT OF 1/4" DOWN CRUSHED LIMESTONE

CONTRACTOR TO CONFIRM ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION. LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF <u>ALL</u> SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

	DRAWING NO.
OVEMENTS	F.32-B
	BID OPPORTUNITY NO.