

1.0 GENERAL REQUIREMENTS

1. The Specification covering the General Conditions of the Contract, Supplementary Conditions, General and Safety Requirements, Instructions to Bidders, and all sections form an integral part of this Specification and shall be read in conjunction herewith.
2. Division 28 shall comply with the general requirements listed within Division 26.

1.1 FIRE ALARM SYSTEM

1. The Electrical Subcontractor shall install new devices or relocate existing as indicated on the Drawings. All audible, alarm or supervisory zones that have been altered or added to shall be reverified by an agent acceptable to the Contract Administrator. The cost of this reverification shall be included in the Contract Price.
2. The Reverification Report shall accompany the record Drawings.
3. Provide written confirmation of monitoring or Schedule A with City of Winnipeg, where required.
4. All new fire alarm devices shall match existing.
5. Where fire alarm devices are deleted, provide red coverplate and ensure continued accessibility. Paint coverplates of all fire alarm junction boxes, this area red.
6. All new and/or relocated fire alarm devices shall be listed and locations shown on a separate drawing to be issued to the City.
7. Provide separate zone where new fire wall shown and connect to new zone on existing system.

END OF SECTION