



- Mushroom play elements to remain in place
- **Strapping around existing trees identified with red circles**
- Remove existing picnic table and concrete pad (by others)
- Excavate existing sand safety surface around existing elephant climber (10 CM). Elephant climber to remain in place.
- Remove existing single tier timbers (by others)
- Excavate sand safety surface to 150 MM depth (17 CM)
- Remove existing bench (by others)
- Remove existing concrete pad (3.25 SM)
- Remove existing wood bollards and chains (60 EA)
- Excavate existing sand safety surface to min. 150 MM depth (11 CM)
- Construction access from back lane
- Remove existing bench (by others)
- Remove existing concrete pad (3.25 SM)
- Remove pea gravel safety surface to min. 150 MM depth (14 CM)
- Remove existing two- tier timbers (37 LM) (by others)

CONTRACTOR TO CONFIRM ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION. LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.



THE CITY OF WINNIPEG  
 Planning, Property and Development Department  
 Planning and Land Use Division  
 Unit 15 - 30 Fort Street, Winnipeg, MB, (R3C 4X5)

DESIGNED BY	IM	CHECKED BY	IL
DRAWN BY	IM	APPROVED BY	IL
HORIZ. SCALE	1:500		
VERT. SCALE			
DATE	May 2017		

MANAGER, PARK AND OPEN SPACES	DATE
MANAGER, PLANNING AND LAND USE DIVISION	DATE

DRAWING TITLE <b>Isbister Park Playground Redevelopment Removals</b>
SITE ADDRESS 534 Hamilton

DRAWING NO. <b>I.013-2</b>
BID OPPORTUNITY NO. 416-2017