

Appendix B - Design Conditions

Sewer Details													Design Conditions					
DWG	Sewer Asset	Street Name	Location	Manholes				Length	Size		Shape	Flow Type	Material	Installation of New MH's	Max Depth	Pre EPR Ovality	Post EPR Ovality	PD/FD ¹
				Upstream	Depth	Downstream	Depth		Height	Width								
11748	S-MA60000352	ROBINDALE RD	1ST MH S OF BETSWORTH AV TO 2ND MH S OF BETSWORTH AV	S-MH6000198	3.78	S-MH60000199	4.06	74.7	200		CIRCULAR	SANITARY	CONCRETE		4.06	2%		FD
11749	S-MA60002011	BEIKO AV	MN @ DONNINGTON RD TO MH @ ELMHURST RD (E.PL)	S-MH60001461	6.04	S-MH60001460	6.62	75.0	250		CIRCULAR	SANITARY	CONCRETE		6.62	6%		FD
11750	S-MA60002519	HANEY ST	MH @ HEWITT CR - MH @ OSWALD BY	S-MH60001866	4.00	S-MH60001875	4.51	122.4	200		CIRCULAR	SANITARY	CONCRETE		4.51	2%		FD
11751	S-MA60002792	LAXDAL RD	1ST MH S OF GRANT AV TO MH @ GRANT AV	S-MH60002049	5.75	S-MH60002053	6.81	122.1	200		CIRCULAR	SANITARY	CONCRETE		6.81	2%		FD
11752	S-MA60002813	LAXDAL RD	1ST MH S OF PARKIN AV - 2ND MH S OF PARKIN AV	S-MH60002065	3.43	S-MH60002064	4.00	122.0	200		CIRCULAR	SANITARY	CONCRETE		4.00	2%		FD
11753	S-MA60002935	CATHCART ST	2ND MH S OF PARKIN AV TO MH @ BOYER AV	S-MH60002143	6.86	S-MH60002144	6.76	84.9	400		CIRCULAR	SANITARY	AC-ASBESTOS CEMENT		6.86	3%		PD
11754	S-MA60003595	CATHCART ST	MH @ ROBLIN BV TO 1ST MH S OF ROBLIN BV	S-MH60002603	3.37	S-MH60002608	3.28	53.7	250		CIRCULAR	SANITARY	CONCRETE		3.37	2%		FD
11755	S-MA60003650	BATCHELOR AV	1ST MH W OF OAKDALE DR TO MH AT OAKDALE DR	S-MH60002649	4.96	S-MH60002650	5.45	90.7	200		CIRCULAR	SANITARY	CONCRETE		5.45	8%		FD
11756	S-MA60003871	ROW E RIDGEDALE	1ST MH W BISHOPS LN - MH @ RIDGEDALE CR	S-MH60002667	6.14	S-MH60002772	6.57	66.4	200		CIRCULAR	SANITARY	AC-ASBESTOS CEMENT		6.57	2%		FD
11757	S-MA60006279	ALDRSHOT BV	MH AT HOLDSWORTH AV-1ST MH N OF HOLDSWORTH AV	S-MH60004913	5.34	S-MH60004918	5.70	99.6	250		CIRCULAR	SANITARY	CONCRETE		5.70	4%		FD
11758	S-MA60007351	LANE (S.OF CORYDON AV)	1ST MH W OF SOUTHPORT BV TO MH @ SOUTHPORT BV	S-MH60005914	2.84	S-MH60005968	3.18	47.6	200		CIRCULAR	SANITARY	CONCRETE		3.18	16%	2%	FD
11759	S-MA70124492	TUXEDO AV	1ST MH E OF EDGELAND BV TO 1ST MH W OF EDGELAND BV	S-MH70060835	3.22	S-MH70060836	3.16	146.4	300		CIRCULAR	COMBINED	CONCRETE		3.22	10%	10%	FD
11760	S-MA60015560	TOWNSEND AV	1ST MH E TO MH AT AURORA ST	S-MH60013293	3.18	S-MH60013283	5.49	99.7	200		CIRCULAR	SANITARY	CONCRETE		5.49	8%		FD
11761	S-MA60015571	SILVERSTONE AV SPL	1ST MH E TO TOWNSEND AV - MH @ AURORA ST	S-MH60013291	1.52	S-MH60013279	2.00	86.0	375		CIRCULAR	STORM	CONCRETE		2.00	4%		FD
11762	S-MA60015601	SILVERSTONE AV SPL	MH @ LEACH ST - 1ST H LEACH ST	S-MH60013317	2.57	S-MH60013322	0.00	46.3	525		CIRCULAR	STORM	CONCRETE		2.57	3%		PD
11763	S-MA60015619	APRIL ST	1ST MH N OF PASADENA AV TO MH AT PASADENA AV	S-MH60013337	2.42	S-MH60013338	3.54	91.4	200		CIRCULAR	SANITARY	CONCRETE		3.54	7%	7%	FD
11764	S-MA60017296	CLARENCE AV	1ST MH E OF HUDSON ST - 2ND MH E OF HUDSON ST	S-MH60014922	4.58	S-MH60014930	4.61	93.6	250		CIRCULAR	SANITARY	CONCRETE		4.61	2%		FD
11765	S-MA60017317	HUDSON ST	1ST MH N OF KELSEY AV TO 1ST MH N OF KELSEY AV	S-MH60014946	2.48	S-MH60014945	2.64	65.2	250		CIRCULAR	SANITARY	CONCRETE		2.64	2%		FD
11766	S-MA60017283	HOWARD AVE	1ST MH E OF HUDSON ST TO 2ND MH E OF HUDSON ST	S-MH60014912	3.96	S-MH60014983	4.19	106.7	200		CIRCULAR	SANITARY	CONCRETE		4.19	3%		PD
11767	S-MA60017357	HOWARD AVE	1ST MH W OF PEMBINA HWY TO MH AT PEMBINA HWY	S-MH60014983	4.19	S-MH60014984	5.77	29.3	250		CIRCULAR	SANITARY	CONCRETE		5.77	8%		FD
11768	S-MA60017364	PEMBINA HWY	MH AT KELSEY AV TO MH AT HOWARD AV	S-MH60015032	5.00	S-MH60014984	5.77	93.9	250		CIRCULAR	SANITARY	VITRIFIED CLAY		5.77	15%		FD
11769	S-MA60017380	PEMBINA HWY	1ST MH N OF WALLERAY TO MH AT WALLER AV	S-MH60015006	3.97	S-MH60015003	4.04	101.9	250		CIRCULAR	SANITARY	CONCRETE		4.04	2%	2%	FD
11770	S-MA60017555	SANDRA BAY (W. LEG)	1ST MH N OF CRANE AV TO MH AT CRANE AV	S-MH60015195	3.67	S-MH60015178	6.18	61.2	200		CIRCULAR	SANITARY	CONCRETE		6.18	10%		FD
11771	S-MA60017686	BUXTON RD	2ND MH S DOWKER AV - 3RD MH S DOWKER AV	S-MH60015298	4.02	S-MH60015311	4.06	111.9	200		CIRCULAR	SANITARY	VITRIFIED CLAY		4.06	10%	10%	FD
11772	S-MA60017675	BUXTON RD	3RD MH S DOWKER AV - MH @ CRANE AV NPL	S-MH60015311	4.06	S-MH70065595	0.00	92.7	200		CIRCULAR	SANITARY	VITRIFIED CLAY		4.06	20%	11%	FD
11773	S-MA70131572	BUXTON RD	MH AT CRANE AV (N PL) TO MH AT CRANE AV (S CURB)	S-MH70065595	0.00	S-MH60015302	6.55	16.1	200		CIRCULAR	SANITARY	CONCRETE		6.55	8%	8%	FD
11774	S-MA60018046	MARSHALL BAY	MH AT BRISBANE AV TO MH AT CLARENCE AV	S-MH60015621	3.66	S-MH60015631	4.18	86.0	200		CIRCULAR	SANITARY	CONCRETE		4.18	14%		FD
11775	S-MA60018077	BRISBANE AVE	1ST MH E OF BELAIR RD TO MH AT BELAIR RD	S-MH60015696	2.50	S-MH60015652	0.00	42.6	200		CIRCULAR	SANITARY	CONCRETE		2.50	6%		FD
11776	S-MA60018189	ROYSE AV	MH @ HUDSON ST - 1ST MH E HUDSON ST	S-MH60015758	3.98	S-MH60015756	4.45	80.8	250		CIRCULAR	SANITARY	CONCRETE		4.45	5%		FD
11777	S-MA60018206	BOSTON AVE	1ST MH E OF HUDSON ST TO MH AT HUDSON ST	S-MH60015772	3.06	S-MH60015777	3.58	90.5	200		CIRCULAR	SANITARY	PVC		3.58	10%	10%	FD
11778	S-MA232-0022	PEMBINA HWY	MH AT CHEVRIER BV (SPL) TO MH AT CHEVRIER BV	S-MH70036027	4.80	S-MH60015826	4.88	14.8	300		CIRCULAR	SANITARY	VITRIFIED CLAY		4.89	3%		PD
11779	S-MA60018237	PEMBINA HWY	MH AT MANAHAN AV - MH AT CHEVRIER BV	S-MH60015801	4.51	S-MH70036027	4.80	121.6	300		CIRCULAR	SANITARY	VITRIFIED CLAY		4.80	3%		PD
11780	S-MA60018271	LANE (BTWN. BOSTON & ROYSE)	MH AT PEMBINA HWY(WPL)-MH AT PEMBINA HWY	S-MH60015836	5.93	S-MH60015837	5.98	22.0	450		CIRCULAR	SANITARY	VITRIFIED CLAY		5.98	2%		FD
11781	S-MA70032571	MAPLERIDGE AV	1ST MH W OF ULSTER ST - MH AT ULSTER ST	S-MH60017363	3.96	S-MH60017007	4.57	91.6	250		CIRCULAR	SANITARY	CONCRETE		4.57	2%		FD
11782	S-MA60018944	ROCHESTER AV	1ST MH W OF RYERSON AV TO MH AT DALHOUSIE DR	S-MH60016427	5.55	S-MH60016379	5.76	101.2	250		CIRCULAR	SANITARY	CONCRETE		5.76	17%	2%	FD
11783	S-MA60019515	VASSAR RD	1ST MH N OF LINACRE RD TO MH AT LINACRE RD	S-MH60016916	2.40	S-MH60016917	2.38	27.2	200		CIRCULAR	SANITARY	CONCRETE		2.40	10%	2%	FD
11784	S-MA60019519	FORDHAM BAY (S LEG)	MH @ FORDHAM BV (ELG) TO 1ST MH E OF CORNELL DR	S-MH60016920	2.90	S-MH60017306	3.51	79.1	200		CIRCULAR	SANITARY	CONCRETE		3.51	8%		FD
11785	S-MA60019538	KILKENNY DR	2ND MH N OF RADCLIFFE RD TO 1ST MH N OF RADCLIFFE RD	S-MH60016944	3.68	S-MH60016945	4.21	58.7	200		CIRCULAR	SANITARY	CONCRETE		4.21	9%		FD
11786	S-MA60019535	KILKENNY DR	1ST MH N OF RADCLIFFE RD TO MH AT RADCLIFFE RD	S-MH60016945	4.21	S-MH60016938	4.02	58.8	200		CIRCULAR	SANITARY	CONCRETE		4.21	11%	3%	PD
11787	S-MA60019640	BRIAR CLIFF BAY (S LEG)	MH@BRIAR CLIFF BY(WLGT)O MH@ BRIAR CLIFF BY(ELG)	S-MH60017045	2.97	S-MH60017139	3.03	102.9	200		CIRCULAR	SANITARY	CONCRETE		3.03	2%		FD
11788	S-MA60019775	PURDUE BAY (N LEG)	MH @ PURDUE BV (ELG) TO 1ST MH E OF DALHOUSIE DR	S-MH60017177	3.38	S-MH60017170	3.82	94.8	200		CIRCULAR	SANITARY	CONCRETE		3.82	21%	2%	FD
11789	S-MA60019813	RUTGERS BAY (E LEG)	MH @ RUTGERS BY(SLG) (NPL)O MH@ RUTGERS BY (NLG)	S-MH60017214	3.34	S-MH60017215	3.04	81.0	200		CIRCULAR	SANITARY	CONCRETE		3.34	2%		FD
11790	S-MA60019865	BALDRY BAY (N LEG)	1ST MH W OF CORNELL DR TO MH AT BALDRY BY (WLG)	S-MH60017264	2.92	S-MH60017271	2.93	84.4	200		CIRCULAR	SANITARY	CONCRETE		2.93	7%	2%	FD
11790	S-MA60019872	BALDRY BAY (N LEG)	1ST MH W OF CORNELL DR TO MH AT CORNELL DR	S-MH60017271	2.93	S-MH60017272	2.98	83.9	200		CIRCULAR	SANITARY	CONCRETE		2.98	17%	2%	FD
11792	S-MA70076036	CORNELL DR (EPL TO CL)	2ND MH S OF SILVERSTONE AV TO 3RD MH S OF SILVERSTONE AV	S-MH60017268	3.31	S-MH60017254	6.59	14.2	200		CIRCULAR	SANITARY	CONCRETE		6.59	7%		FD
11793	S-CL60023129	PEMBINA HWY E OF CL	2ND CB S OF LEMAY AV TO MH AT DE LEGLISE AV N OF	S-CB60019391	1.84	S-CB60019384	1.99	19.8	200		CIRCULAR	STORM	CSP		1.99	54%	8%	FD
11794	S-CL60023119	PEMBINA HWY E OF CL	2ND CB S OF LEMAY AV TO MH AT DE LEGLISE AV N OF	S-CB60019384	1.99	S-MH60019383	2.13	27.3	250		CIRCULAR	STORM	CSP		2.13	7%		FD
11795	S-MA60023118	PEMBINA HWY E OF CL	MH AT DE LEGLISE AV S OF CL TO MH AT DE LEGLISE	S-MH60019383	2.13	S-MH60019000	2.77	14.0	300		CIRCULAR	STORM	CMP		2.77	9%	9%	FD
11796	S-MA60023124	PEMBINA HWY E OF CL	1ST MH S OF DE LEGLISE AV TO MH AT DE LEGLISE AV	S-MH60019000	2.77	S-MH60019386	3.96	35.5	300		CIRCULAR	STORM	CMP		3.96	17%		FD
11797	S-MA60021988	ST THERESE AVE	3RD MH W OF ST PIERRE ST TO MH @ LA BARRIERE ST	S-MH60018649	4.16	S-MH60018650	5.08	87.1	250		CIRCULAR	SANITARY	CONCRETE		5.08	12%		FD
11798	S-MA60022033	LEMAY AV	1STMH E OF LA BARRIERE ST TO MH @ LA BARRIERE ST	S-MH60018690	5.84	S-MH60018688	5.87	103.4	250		CIRCULAR	SANITARY	CONCRETE		5.87	18%		FD
11799	S-MA60022032	LEMAY AV	1STMH W OF ST PIERRE ST TO 2ND MH W OF ST PIERREST	S-MH60018689	5.67	S-MH60018690	5.84	101.8	250		CIRCULAR	SANITARY	CONCRETE		5.84	17%	12%	FD
11800	S-MA60022274	CLOUTIER DR	1ST MHE OF STORMONT TO 2ND MHE OF STORMONT	S-MH60018720	3.18	S-MH60018721	4.16	98.1	250		CIRCULAR	SANITARY	CONCRETE		5.18	2%		FD
11801	S-MA60023213	LESTANG ST	MH @ HOUE DR - MH @ GENDREAU AV	S-MH60019467	3.17	S-MH60019462	4.26	91.2	200		CIRCULAR	SANITARY	CONCRETE		4.26	2%		FD
11802	S-MA60023225	DES TRAPPISTES ST	1ST MH W OF VILLENEUVE TO 2ND MH W OF VILLENEUVE	S-MH60019477	4.90	S-MH60019476	5.32	68.0	250		CIRCULAR	SANITARY	CONCRETE		5.32	2%		FD
11803	S-MA60023223	VILLENEUVE BLVD	MH AT RUE DES TRAPPISTES TO 1ST MH S OF GENDREAU	S-MH60019474	4.96	S-MH60019475	5.24	97.8	250		CIRCULAR	SANITARY	CONCRETE		5.24	2%		FD
11804	S-MA60023238	DES TRAPPISTES ST	MH AT VILLENEUVE BV TO 1ST MH E OF VILLENEUVE BV	S-MH60019475	5.24	S-MH60019488	5.79	46.0	250		CIRCULAR	SANITARY	CONCRETE		5.79	2%		FD
11805	S-MA60023239	DES TRAPPISTES ST	1ST MH E OF VILLENEUVE BV TO 1ST MH W OF PEMBINA	S-MH60019488	5.79	S-MH60019489	5.74	76.5	250		CIRCULAR	SANITARY	CONCRETE		5.79	2%		FD
11818	S-MA60003689	ROW W BISHOPS LN	MH @ BISHOPS LN - 1ST MH W BISHOPS LN	S-MH60002668	7.36	S-MH60002667	6.12	82.6	200		CIRCULAR	SANITARY	AC-ASBESTOS CEMENT		7.36	2%		FD