



- SUPPLY & INSTALL SINGLE TIER TIMBER EDGING (11 LM) PER SCD-651 & SCD-651B
- SUPPLY & INSTALL PARKWAY PATH CRUSHED LIMESTONE (14 SM) PER SCD-646
- PICK UP & INSTALL 1 BENCH PER SCD-121A & SCD-136A
- SUPPLY & INSTALL MINIMUM 100 mm DEPTH WOODCHIP MULCH (13 SM) PER SCD-501
- SUPPLY & INSTALL 13 VARIEGATED REED GRASS @ 1m O.C. AND SHRUB BED (15 SM) PER SCD-501

LEGEND

- SINGLE TIER TIMBER EDGING C/W CAP
- DOUBLE TIER TIMBER EDGING C/W CAP
- DOUBLE TIER TIMBER EDGING, NO CAP
- LANDING
- SUPPLY & INSTALL NEW CHAIN LINK FABRIC (64 LM) PER CW 3550
- SUPPLY & INSTALL NEW 1.5 m (5') CHAIN LINK FENCE (24 LM) PER CW 3550
- EXISTING TREES - MAINTAIN & PROTECT AS PER CW 1130

- SUPPLY & INSTALL MINIMUM 100 mm DEPTH WOODCHIP MULCH (36 SM) PER SCD-501
- OFFSET NEW 1.5 m CHAINLINK FENCE 150 mm FROM PROPERTY LINE. CONFIRM PROPERTY SURVEY PINS WITH CITY OF WINNIPEG GEOMATICS BRANCH PRIOR TO CONSTRUCTION.
- SUPPLY & INSTALL 2-12 YEAR PLAYGROUND EQUIPMENT
- SUPPLY & INSTALL DOUBLE TIER TIMBER EDGING (81 LM) PER SCD-651A & SCD-651B
- SUPPLY & INSTALL ENGINEERED WOOD FIBRE SAFETY SURFACING (257 SM) C/W ADDITIONAL 150 mm GRANULAR DRAINAGE

1
S.60-B3

Plant Specification List

Common Name	Botanical Name	Qty	Size	Remarks
PERENNIALS				
VARIEGATED REED GRASS	Calamagrostis x acutiflora 'Overdam'	13	1 gal	2 YEAR PLANTS FROM DIVISION 1 GRADE, WELL DEVELOPED, VIGOROUS ROOT SYSTEM, PLANTED Per SCD-501.

MATERIALS NOTES

1. ALL WORK TO CONFORM TO CURRENT CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS AND DETAILS UNLESS OTHERWISE NOTED.
2. DIMENSIONS ARE IN METERS UNLESS OTHERWISE NOTED.
3. REPORT ANY DISCREPANCIES TO THE CONTRACT ADMINISTRATOR IMMEDIATELY.
4. DO NOT SCALE DRAWING.
5. PROTECT EXISTING TREES TO REMAIN AS PER CW 1130.
6. ACCESSIBLE PLAYGROUND RAMP PER SCD-656
 - i) REMOVE ALL EXISTING ORGANIC MATERIAL TO AN APPROX. DEPTH OF 75mm.
 - ii) APPROXIMATELY 3 CUBIC METERS OF 50 mm (2") DOWN CRUSHED LIMESTONE SUB-BASE REQUIRED TO MEET DESIGN GRADES, SEE S.60-B4.

CONTRACTOR TO CONFIRM ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION. LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.



THE CITY OF WINNIPEG
 Planning, Property and Development Department
 Planning and Land Use Division
 Unit 15 - 30 Fort Street, Winnipeg, MB, (R3C 4X5)

DESIGNED BY	LL	CHECKED BY	
DRAWN BY	LL	APPROVED BY	
HORIZ. SCALE	1:200		
VERT. SCALE			
DATE	April 2018		

MANAGER,
PARK AND OPEN SPACES

DATE

MANAGER,
PLANNING AND LAND USE DIVISION

DATE

DRAWING TITLE
**Scouts Park
 Playground Redevelopment
 Materials Plan**

SITE ADDRESS 110 Winona Street

DRAWING NO.
S.60-B2

BID OPPORTUNITY NO.
53-2018