

640-2018 ADDENDUM 2

CONSTRUCTION OF TRUNK SEWER AND LDS SEPARATION – COCKBURN & CALROSSIE SEWER RELIEF WORKS (CONTRACT 11)

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE BID
OPPORTUNITY**

ISSUED: Sep.27, 2018
BY: Ray Offman
TELEPHONE NO. 204-896-1209

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID OPPORTUNITY AND SHALL
FORM A PART OF THE CONTRACT
DOCUMENTS**

Template Version: A20160708

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid Opportunity, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

PART A – BID SUBMISSION

Replace: 640-2018 Bid Submission with 640-2018 Addendum 2 - Bid Submission. The following is a summary of changes incorporated in the replacement Bid Submission:

Form B (R1):

- Revised type of bedding and foundation material for all Trenchless Sewer Construction main line items that include installation of PVC SDR35 pipe to read Type 2 bedding rather than Type 3 bedding.
- Decreased quantity of 150 mm Watermain Valve (A.17.a)
- Added Connection to Existing Watermains (Inline Connection – No Plug Existing) (A19)
- Added New 150 mm Watermain Valve on Existing Watermain (A20.a)

Page numbering on some forms may be changed as a result.

PART B – BIDDING PROCEDURES

Revise: B18.5 (Addendum 1) Further to B18.1(c), where the Evaluated Total Bid Price exceeds the funds stated in D3.1.1, the City may determine that no award will be made in accordance with B19.2.1(a).

PART D – SUPPLEMENTAL CONDITIONS

Add: D2.11 The Contractor is to take due care when working near the existing large diameter (500 mm) A.C. feeder watermain on the south side of Grant Avenue. Installation equipment for the proposed Works shall not cross or travel along either side of the large diameter watermain within a lateral distance of 5.0 m from the centreline of the large diameter watermain. The Contractor shall not operate vibratory equipment over or within 3.0 m of the large diameter watermain centreline.

Revise: D20.1(a) Critical Stage 1 : June 1, 2019 – The Contractor shall complete all work or material/equipment storage on Wilton Street between the existing concrete caisson and Taylor Avenue by this date.

- (i) Cockburn Contract 5 is scheduled to commence in the spring of 2019. In order to facilitate the local and regional vehicular flows, construction activities will not be permitted adjacent to Taylor Avenue.

Add: D20.1(a)(ii) Access to Wilton Street from Taylor Avenue will not be permitted once Cockburn Contract C5 commences with the exception of an overnight shutdown (subject to approval by the City).

Revise: D24.1.1(c) Final Span: Means the number of Charged Days assessed for Site Occupancy as calculated pursuant to **D24.3**.