



3/8" ϕ AIRCRAFT CABLE
CUT LENGTH = 2500
TOTAL REQUIRED = 1
TOTAL LENGTH = 2.5m

LIFT HOOK DETAIL

SEE ATTACHED REINFORCING SCHEDULE(S) FOR ALL REINFORCING BAR SHAPES, SIZES AND QUANTITIES.									
UNLESS NOTED OTHERWISE ALL TOLERANCES = CSA A23.4-09 (CL.12)									
MARK No.	QUANTITY	LENGTH (mm)	VOLUME (m ³)		MASS (kg)				
		AREA (m ²)	FACE	BACK					
LOCK BLK-02	TO BE DETERMINED	1.2	-	0.88	2115				
CONCRETE DATA		WPG. MIX DESIGN NO.	85	LIFT HOOK					
CEMENT TYPE:	GU	AIR ENTRAINMENT:	6.5% \pm 1.5	STRAND LIFT HOOK					
RELEASE STR. (MIN.):	20 MPa	MAX. AGGREGATE:	14mm	DIAMETER:	3/8" ϕ				
28 DAY STR (MIN.):	40 MPa	MAX. W/C RATIO:	0.33	LENGTH:	2.5 m				
MARK #	QTY./UNIT	MARK #	QTY./UNIT	MARK #	QTY./UNIT	MARK #	QTY./UNIT	MARK #	QTY./UNIT
-	-								
STOCK ITEMS									
QTY./UNIT	DESCRIPTION								
-	-								
A RELEASED FOR APPROVAL				JR	2013.07.23				
REV.	DESCRIPTION				BY	DATE			
<div style="border: 1px solid black; padding: 5px; display: inline-block;"> RELEASED for APPROVAL DATE: JULY 23, 2013 ARMTEC </div>									
IMPERIAL LOCK BLOCK									
BRADY ROAD RESOURCE MANAGEMENT FACILITY									
									
DRAWN BY	ENG. REVIEW	CHECKED BY	DATE						
JR			2013.07.22						
SAP No.	DWG. No.		REV						
	LOCK BLK-02		0						