



Sewer Junction Information
(From Video Inspection)

Reference MH	Distance	Size	Clock
S-MH50011462	007.0	150	10
-	010.0	150	02
-	019.2	150	11
-	023.8	150	01
-	036.1	150	11
-	038.4	150	02
-	038.4	150	11
-	053.6	150	02
-	053.7	150	10
-	062.5	150	01
-	076.8	150	11
-	080.3	150	11
-	094.2	150	11
-	095.0	150	01
-	106.7	150	01

Traffic Controls
Regional Street Lane Closure Required: No
Impacted Regional Street: N/A

General Requirements:
Residential Street Restrictions.

WARNING
IF POWER EQUIPMENT OR EXPLOSIVES ARE TO BE USED FOR EXCAVATION ON THIS PROJECT, THE CONTRACTOR MUST:
1) NOTIFY THE GAS COMPANY OF THE PROPOSED LOCATION OF EXCAVATION
2) TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY INSTALLATIONS
SEE PROVINCIAL REGULATION 140/92 FOR DETAILS

AECOM
Certificate of Authorization
AECOM Canada Ltd.
No. 4671 Date: 04/04/2019

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES
0 2.5 5 10 15 20
Meters
TENDER NO. 183-2019

AECOM REVIEW DRAFT CHK
FILE NAME: 2018 Lining - C6.pdf SAVED BY: ES

LOCATION APPROVED UNDERGROUND STRUCTURES

NO.	ISSUED FOR CONSTRUCTION	DATE	BY
0	ISSUED FOR CONSTRUCTION	19/04/01	ES
NO.	REVISIONS	YY/MM/DD	BY

AECOM

DESIGNED BY	NK	CHECKED BY	AIB
DRAWN BY	ES	APPROVED BY	dn
HOR. SCALE	1:500	RELEASED FOR CONSTRUCTION	APR 3/19
VERT. SCALE	N/A	DATE	APR 3/19

PROFESSIONAL'S SEAL

Signature
N.J.
KEHLER
Member
30100
APR 4 2019
REGISTERED PROFESSIONAL ENGINEER

CONSULTANT DRAWING NO.
60592016-01-C-2018 Lining - C6-R0.mxd

THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT

2018 SEWER RENEWALS
BY CIPP LINING
CONTRACT 6
SPRINGSIDE DR
1ST MH E OF KILLARNEY TO 2ND MH E OF KILLARNEY

SHEET 9 OF 49
CITY DRAWING NUMBER
12079 REV 0