

Sewer Junction Information

(From Video Inspection)

Reference MH	Distance	Size	Clock
S-MH50004936	000.3	200	06
-	001.2	150	02
S-MH50004937	017.5	150	10
-	033.9	150	10
-	047.2	150	10

Traffic Controls

Regional Street Lane Closure Required: No
Impacted Regional Street: N/A

General Requirements:

Residential Street Restrictions.

WARNING

IF POWER EQUIPMENT OR EXPLOSIVES ARE TO BE USED FOR EXCAVATION ON THIS PROJECT, THE CONTRACTOR MUST:
1) NOTIFY THE GAS COMPANY OF THE PROPOSED LOCATION OF EXCAVATION.
2) TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY INSTALLATIONS.
SEE PROVINCIAL REGULATION 140/92 FOR DETAILS



Certificate of Authorization

AECOM Canada Ltd.

No. 4671 Date: 04/04/2019

METRIC

WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

0 2.5 5 10 15 20

Meters

TENDER NO. 183-2019

LOCATION APPROVED UNDERGROUND STRUCTURES

SUPR. U/G STRUCTURES DATE COMMITTEE


NOTE:
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE. BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

NO.	ISSUED FOR CONSTRUCTION	19/04/01	ES
0	ISSUED FOR CONSTRUCTION	19/04/01	ES
NO.	REVISIONS	YY/MM/DD	BY



DESIGNED BY	NK	CHECKED BY	APB
DRAWN BY	ES	APPROVED BY	An
HOR. SCALE	1:500	RELEASED FOR CONSTRUCTION	APR 3/19
VERT. SCALE	N/A	DATE	APR 3/19

PROFESSIONAL'S SEAL



CONSULTANT DRAWING NO.

60592016-01-C-2018 Lining - C6-R0.mxd

THE CITY OF WINNIPEG WATER AND WASTE DEPARTMENT

2018 SEWER RENEWALS
BY CIPP LINING
CONTRACT 6

AUTUMWOOD DR (S OF CL)
1ST MH W OF BARBERRY RD (E LEG) TO MH AT FRONTENAC BY (W LEG)

SHEET 15 OF 49

CITY DRAWING NUMBER

12085

REV

0

FILE NAME: 2018 Lining - C6.pdf

AECOM REVIEW DRFT CHK

SAVED BY: ES