

GENERAL NOTES:


- 1. IT IS RECOMMENDED THAT THE BIDDERS EXAMINE THE SITE & EXISTING CONDITIONS THAT AFFECT THE PROJECT. EXAMINE THE COMPLETE SET OF CONTRACT DOCUMENTS TO ENSURE THAT THE WORK CAN BE CARRIED OUT WITHOUT SIGNIFICANT CHANGES TO THE INTENT OF THE DOCUMENTS. NO FUTURE ALLOWANCE WILL BE MADE FOR CHANGES UNLESS THE ENGINEER HAS BEEN NOTIFIED IN WRITING OF ANY DISCREPANCIES OR INTERFERENCES PRIOR TO THE CLOSE OF TENDERS. NO ALLOWANCE WILL BE MADE FOR ITEMS THAT SHOULD HAVE BEEN NOTED DURING PRE—TENDER SITE INSPECTION.
- THE LOCATION, ROUTING & ELEVATION OF ALL NEW AND EXISTING SERVICES & UTILITIES AS SHOWN ON THE DRAWING ARE TO BE CONSIDERED AS APPROXIMATIONS ONLY. VERIFY EXACT LOCATIONS, ROUTINGS & ELEVATIONS OF ALL SERVICES PRIOR TO COMMENCING WORK. THE CONTRACTOR SHALL RETAIN RESPONSIBILITY FOR ANY DAMAGE TO EXISTING SERVICES AND UTILITIES.
 ALL ASPECTS OF THE INSTALLATION MUST COMPLY WITH THE MOST STRINGENT OF THE APPLICABLE BUILDING CODES, LOCAL REGULATIONS, BY-LAWS, & BUILDING GUIDELINES.
- 4. PROVIDE ALL LABOR, MATERIALS, & EQUIPMENT NECESSARY TO COMPLETE THE WORK SHOWN ON DRAWINGS & AS SPECIFIED HEREIN.
- COORDINATE EXACT ROUTING OF DUCTWORK WITH PIPING, SITE CONDITIONS, ALL OTHER TRADES, ETC.
- COORDINATE EXACT LOCATION OF GRILLES AND DIFFUSERS ON SITE WITH THE ELECTRICAL SUBCONTRACTOR, CONTRACTOR, ARCHITECTURAL REFLECTED CEILING PLAN, LIGHTING LANGUAGE THAT THERE ARE NO CONFLICTS DURING INSTALLATION.
- 7. PROVIDE BALANCE DAMPERS AS SHOWN AND AS REQUIRED TO ALLOW PROPER BALANCING OF THE SYSTEMS. PROVIDE OPPOSED BLADE DAMPERS WITH THE DIFFUSER AND ADJUSTABLE FROM THE DIFFUSER FACE WHEN A DUCT MOUNTED BALANCE DAMPER WOULD NOT BE ACCESSIBLE.
- AN AABC CERTIFIED BALANCE CONTRACTOR SHALL BALANCE THE SYSTEM TO PROVIDE THE INDICATED AIR FLOWS.
- ALL DUCT DIMENSIONS DENOTE INTERNAL "FREE" AREA OF THE DUCT.

- 10. ALL DUCTWORK, UNLESS OTHERWISE NOTED, PENETRATING THE BUILDING THERMAL ENVELOPE SHALL BE INSULATED FOR A MINIMUM DISTANCE OF 10'-0" BACK FROM THE BUILDING PENETRATION. INSULATION TO BE AS SPECIFIED IN MECHANICAL SPECIFICATIONS.
- DAMPERS IN ALL WALLS DENOTED AS FIRE SEPARATIONS WHETHER SHOWN ON THE MECHANICAL PLANS OR NOT. 12. COORDINATE THE EXACT LOCATION OF ALL MECHANICAL EQUIPMENT, DUCT OPENINGS AND DUCT LOCATIONS WITH

11. REFER TO ARCHITECTURAL DRAWINGS AND PROVIDE FIRE


- 13. PROVIDE SINGLE THICKNESS TURNING VANES WITH A TRAILING EDGE IN ALL "SQUARE ELBOWS". REFER TO MECHANICAL DETAILS FOR CONSTRUCTION.
- PROVIDE FLEXIBLE CONNECTIONS ON THE INLET AND OUTLET OF ALL FANS AND ON THE INLET AND OUTLET OF ALL EQUIPMENT WITH FANS INSIDE.
- DIFFUSER & REGISTER TAG:

QUANTITY MODEL TYPE FACE SIZE AIR CAPACITY NECK SIZE



DRAWING NOTES:

- 550x300 E/A DUCT UP TO MAIN FLOOR TIGHT TO CORNER OF JANITOR ROOM. COORDINATE FINAL INSTALLATION W/ ARCHITECT, INTERIOR DESIGNER, & ALL OTHER DISCIPLINES.
- 2 4500 TRANSFER AIR DUCT DOWN TO SERVE CRAWLSPACE FROM $\overline{\text{1F}-1}$ IN MPR STORAGE ROOM ABOVE.







Bill and Helen Norrie Library Project No.: 2017-082

Tender No.: 542-2019

Address: 15 Poseidon Bay, Winnipeg, MB.

CRAWLSPACE - HVAC LAYOUT

Comm. No.: 1847 Plotted on: 7/16/2019 10:51:58 AM

Drawings and specifications, as instruments of service are the property of the Winnipeg Manitoba architects, the copyright in the same being reserved to them. No reproduction ma Canada R3B 0P4 be made without the permission of the architects, and when made, must bear their names. All prints to be returned. t. (204) 942.0681 f. (204) 943 8676 The contractor is to verify dimensions and data noted herein with conditions on the site and is held responsible for reporting any discrepancy to the architects for