1 / MP2.1 NORTH WALKWAY DEMOLITION - ROOF PLUMBING
SCALE: 1 : 100

2 / MP2.1 NORTH WALKWAY RENOVATION - ROOF PLUMBING
SCALE: 1 : 100

MECHANICAL DRAWINGS

PLUMBING DRAWINGS
MP2.1 NORTH WALKWAY - ROOF PLUMBING PLAN
MP2.2 SOUTH WALKWAY - ROOF PLUMBING PLAN

HVAC DRAWINGS
MH2.1 NORTH WALKWAY - HVAC PLAN
MH2.2 SOUTH WALKWAY - HVAC PLAN

KEY NOTES

1 REMOVE EXISTING 100 MM RAINWATER ROOF DRAIN. LEAVE EXISTING CAST IRON DRAIN PIPING AS IS.
2 NEW RAINWATER SCUPPER. SEE ARCHITECTURAL.
3 NEW OPENING THROUGH NEW ROOF CURB. SEE ARCHITECTURAL.
4 SUPPLY AND INSTALL NEW ROOF DRAIN WITH 100 MM DISCHARGE CONNECTION. RECONNECT TO EXISTING 100 MM CAST IRON RAINWATER DISCHARGE PIPING.

PLUMBING SYMBOLS

	ROOF DRAIN
EQ / 1i	EQUIPMENT TAG
?	KEY NOTE
?	DEMOLITION NOTE

Cibinel Architecture Ltd
560 ACADEMY ROAD WINNIPEG MB R3N 0E3
T. 204 989 8910

ARCHITECT

Winnipeg

CLIENT

epp siepman engineering
400 - 136 Market Avenue
Winnipeg, MB R3B 0P4
T 204 453 1080

CONSULTANT

N

APEGM
Certificate of Authorization
Epp Siepman Engineering Inc.
No. 4035

This is a print of a document that has been electronically authenticated with technology authorized by the APEGM. The original is in electronic form.

PROVINCE OF MANITOBA
M.A. HAW
Member
27100
LICENSED PROFESSIONAL ENGINEER
2021-05-05

NO.	DATE	REVISION / ISSUANCE
01	2021.05.05	ISSUED FOR CONSTRUCTION

Seal

Project
CARLTON STREET WALKWAY UPGRADES
155 + 185 Carlton Street / Winnipeg, MB

Bid Opportunity No. 111-2020

Sheet Title
NORTH WALKWAY - ROOF PLUMBING PLAN

Project No.
1943

Sheet
MP2.1