1
EL2.1
NORTH WALKWAY DEMOLITION - LIGHTING
SCALE: 1 : 100

2
EL2.1
NORTH WALKWAY RENOVATION - LIGHTING
SCALE: 1 : 100

GENERAL NOTES

A. ALL MOUNTING HEIGHTS FOR LUMINAIRES ARE TO THE BOTTOM OF THE LUMINAIRE UNLESS NOTED OTHERWISE.

B. REFER TO ARCHITECTURAL ELEVATIONS FOR MOUNTING HEIGHTS OF EXTERIOR OR INTERIOR LUMINAIRES.

C. COORDINATE ALL WORK REQUIRING SHUT-DOWN OF EXISTING SYSTEMS THAT COULD AFFECT EXISTING TENANTS WITH THE DEPARTMENTAL REPRESENTATIVE AT A TIME AND MANNER SUITABLE TO THEM.

D. DEMOLISH ALL LIGHT FIXTURES AS INDICATED.

E. REUSE CIRCUITS FREED UP FROM DEMOLISHED LIGHT FIXTURES.

F. ALL LIFE SAFETY SYSTEMS SHALL BE MAINTAINED AND OPERABLE AT ALL TIMES DURING CONSTRUCTION.

G. DRAWING RECORDS OF THE EXISTING FLOOR PLANS HAVE BEEN COMPILED FROM INFORMATION SUBMITTED BY THE OWNER AND FROM SITE OBSERVATIONS AS NOTED BY THE CONSULTANT. THE ACCURACY OF THESE DRAWING RECORDS IS LIMITED TO THE EXTENT OF KNOWN CONSTUCTION INFORMATION.

H. WHERE EXISTING WIRING AND CONDUIT ARE REUSED, VERIFY CONDITION, FASTENING AND SUPPORT MEET CURRENT CODE REQUIREMENTS.

I. IDENTIFY ALL ELECTRICAL SYSTEMS, CIRCUITS, AND CONDUITS PRIOR TO MAKING NEW CONNECTIONS.

J. CONTRACTOR SHALL SECURE ALL EXISTING UNSUPPORTED WIRING, CONDUIT AND JUNCTION BOXES TO MEET MINIMUM CODE REQUIREMENTS.

KEY NOTES

1 DEMOLISH EXISTING LIGHT FIXTURES BACK TO SOURCE.

2 WIRE AND CONNECT ALL NEW LIGHT FIXTURES TO EXISTING 120/208V 3PH PANEL LPA LOCATED IN THE PARKADE OF THE DELTA HOTEL. UTILIZE CIRCUITS FREED UP FROM DEMOLITION.

3 LIGHT FIXTURE LOCATED ON WALKWAY SOFFIT ABOVE COURTYARD. WIRE AND CONNECT TO EXISTING CIRCUITS FOR EXTERIOR LIGHT FIXTURES ABOVE COURTYARD. CONFIRM FINAL LOCATIONS WITH ARCHITECTURAL.

Cibinel
Architecture Ltd
560 ACADEMY ROAD WINNIPEG MB R3N 0E3
T. 204 989 8910

ARCHITECT

Winnipeg

CLIENT

epp siepman engineering
400 - 136 Market Avenue
Winnipeg, MB R3B 0P4
T 204 453 1080

CONSULTANT

N

APEGM
Certificate of Authorization
Epp Siepman Engineering Inc.
No. 4035

This is a print of a document that has been electronically authenticated with technology authorized by the APEGM. The original is in electronic form.

NO.	DATE	REVISION / ISSUANCE
01	2021.05.05	ISSUED FOR CONSTRUCTION

Seal

Project
CARLTON STREET WALKWAY UPGRADES
155 + 185 Carlton Street / Winnipeg, MB

Bid Opportunity No. 111-2020

Sheet Title
NORTH WALKWAY - LIGHTING PLAN

Project No.
1943

Sheet
EL2.1