GENERAL NOTES

1. HATCHED AREAS ARE NOT IN ARCHITECTURAL SCOPE OF WORK. REFER TO STRUCTURAL, MECHANICAL, AND ELECTRICAL FOR WORK IN THESE AREAS. REFER TO MECHANICAL AND ELECTRICAL DRAWINGS FOR REVISIONS TO ANY MECHANICAL AND ELECTRICAL SERVICES AND DEVICES WITHIN AREAS OF NEW CONSTRUCTION.
2. PATCH, REPAIR, AND MAKE GOOD ANY INTERIOR OR EXTERIOR FINISH AFFECTED BY SCOPE OF DEMO, WORK, OR DAMAGE DURING CONSTRUCTION.
3. ALL EXPOSED STRUCTURAL STEEL, SUPPORT STRUCTURE, METAL DECK, STEEL FRAMING, DOOR FRAMES, WALLS, MECHANICAL & ELECTRICAL SERVICE LINES AND CONDUIT WITHIN WALKWAYS TO BE PAINTED.

KEYNOTES

1. LINE OF ENTRANCE SOFFIT BELOW.
2. LINE OF EXISTING BUILDING FACE ABOVE.
3. ALIGN CURTAINWALL VERTICAL MULLION W/ CENTRELINE OF EXISTING COLUMN TYP.
4. CONTINUOUS STAINLESS STEEL HANDRAIL C/W MOUNTING PLATE. MOUNTED TO EXISTING STEEL HSS COLUMNS AND DIAGONALS. REFER TO DETAIL 4/A102.
5. CONTINUOUS STAINLESS STEEL DUAL HANDRAIL C/W POST AND MOUNTING PLATE. MOUNTED TO EXISTING RAMP CURB AND STAIR. EXTEND MIN. 600MM BEYOND BOTTOM OF RAMP & BOTTOM OF STAIR. REFER TO DETAIL 4/A102.
6. CURTAINWALL W/ DUAL GLAZED SPANDREL PANEL AT BASE.
7. 20GA. SOLID STAINLESS STEEL CLOSURE C/W CONTINUOUS 13 X 25 ANGLE SUPPORT - REMOVABLE W/ TAMPERPROOF FASTENERS.
8. SUPPLY & INSTALL SIDE MOUNTED SCUPPER WALL DRAIN AT EXISTING LOCATION. ADJUST DRAIN HEIGHT TO ACCOMMODATE NEW ROOF ASSEMBLY. REFER TO MECHANICAL. REFER TO DETAIL 3/S502.
9. EXISTING POWER DOOR OPERATORS AND ACTUATORS. REFER TO ELECTRICAL.
10. EXISTING RAMP W/ CURB.
11. EXISTING STAIR.
12. EXISTING FLOORING TO REMAIN.
13. EXISTING RUBBER TILE TACTILE WARNING SURFACE TO REMAIN.
14. EXISTING SLOPE IN STRUCTURE.
15. SUPPLY & INSTALL NEW ROOF SYSTEM AS PER ROOF ASSEMBLIES, DETAILS, AND SPECIFICATIONS.
16. SUPPLY & INSTALL NEW PARAPET AT WALKWAY PERIMETER.
17. SUPPLY & INSTALL NEW FLASHING MEMBRANE AND SHEATHING AT ROOF / WALL INTERFACE.
18. SUPPLY & INSTALL NEW INSULATED CURB WALL ALONG NEW ROOF SYSTEM AND CONVENTION CENTRE CLADDING.
19. SUPPLY & INSTALL NEW PTAC UNIT WITHIN CURTAINWALL. REFER TO MECHANICAL. REFER TO DETAILS 3/S501 & 4/S506.
20. SLOPE WITH TAPERED INSULATION.
21. EDGE OF EXISTING FLOOR.
22. PROVIDE WOOD BLOCKING AS REQUIRED FOR MOUNTING CONTINUOUS STAINLESS STEEL HANDRAILS.

1/A102 SOUTH WALKWAY FLOOR PLAN 1:100

2/A102 SOUTH WALKWAY ROOF PLAN 1:100

3/A102 SOUTH WALKWAY RAMP PLAN 1:50

4/A102 HANDRAIL DETAILS TYP. 1:10

5/A102 ELEVATION HANDRAILS TYP. 1:10

6/A102 RAMP HANDRAILS 1:10

7/A102 SOUTH WALKWAY PLAN DETAIL 1:10

8/A102 SOUTH WALKWAY RAMP SECTION 1:50

Cibinel Architecture Ltd
560 ACADEMY ROAD WINNIPEG MB R3N 0E3
T. 204 989 8910

ARCHITECT

Winnipeg

CLIENT

NO.	DATE	REVISION / ISSUANCE
01	2021.05.05	ISSUED FOR CONSTRUCTION

Tender Package

Seal

PROVINCE OF MANITOBA MICHAEL ACHT 2021-05-04 REGISTERED ARCHITECT

PROVINCE OF MANITOBA CIBINEL ARCHITECTURE LTD. No. 225 APPROVED ARCHITECTURAL CORPORATION

MAA Digital Signature Applied

Project

CARLTON STREET WALKWAY UPGRADES

155 + 185 Carlton Street / Winnipeg, MB

Bid Opportunity No. 111-2020

Sheet Title

SOUTH WALKWAY FLOOR + ROOF PLANS

Project No. 1943

Sheet A102

CIBINEL – Arch D – 24" X 36"