GENERAL NOTES

1. HATCHED AREAS ARE NOT IN ARCHITECTURAL SCOPE OF WORK. REFER TO STRUCTURAL, MECHANICAL, AND ELECTRICAL FOR WORK IN THESE AREAS. REFER TO MECHANICAL AND ELECTRICAL DRAWINGS FOR REVISIONS TO ANY MECHANICAL AND ELECTRICAL SERVICES AND DEVICES WITHIN AREAS OF NEW CONSTRUCTION.
2. PATCH, REPAIR, AND MAKE GOOD ANY INTERIOR OR EXTERIOR FINISH AFFECTED BY SCOPE OF DEMO, WORK, OR DAMAGE DURING CONSTRUCTION.
3. ALL EXPOSED STRUCTURAL STEEL, SUPPORT STRUCTURE, METAL DECK, STEEL FRAMING, DOOR FRAMES, WALLS, MECHANICAL & ELECTRICAL SERVICE LINES AND CONDUIT WITHIN WALKWAYS TO BE PAINTED.

KEYNOTES

1. LINE OF ENTRANCE SOFFIT BELOW.
2. LINE OF EXISTING BUILDING FACE ABOVE.
3. ALIGN CURTAINWALL VERTICAL MULLION W/ CENTRELINE OF EXISTING COLUMN TYP.
4. CONTINUOUS STAINLESS STEEL HANDRAIL C/W MOUNTING PLATE. MOUNTED TO EXISTING STEEL HSS COLUMNS AND DIAGONALS. REFER TO DETAIL 4/A102.
5. CURTAINWALL W/ DUAL GLAZED SPANDREL PANEL AT BASE.
6. 20GA. SOLID STAINLESS STEEL CLOSURE C/W CONTINUOUS 13 X 25 ANGLE SUPPORT - REMOVABLE W/ TAMPERPROOF FASTENERS
7. EXISTING DOORS, FRAMES, AND SUPPORT STRUCTURE TO BE PAINTED.
8. SUPPLY & INSTALL NEW ROOF DRAIN AT EXISTING LOCATION. ADJUST DRAIN HEIGHT TO SUIT NEW ROOF ASSEMBLY. REFER TO MECHANICAL.
9. EXISTING POWER DOOR OPERATORS AND ACTUATORS. REFER TO ELECTRICAL.
10. EXISTING FLOOR TILE TO REMAIN.
11. CONTINUOUS STAINLESS STEEL DUAL HANDRAIL C/W MOUNTING PLATE. MOUNTED TO EXISTING STEEL HSS COLUMNS AND DIAGONALS. EXTEND MIN. 600MM BEYOND BOTTOM OF RAMP. REFER TO DETAIL 4/A102.
12. SUPPLY & INSTALL NEW 2MM ALUMINUM CAP FLASHING. EXTEND ROOF FLASHING MEMBRANE OVER CAP FLASHING AND TERMINATE FLUSH WITH THE EXTERIOR EDGE. BOTTOM OF SCUPPER TO BE 61MM ABOVE ROOF DRAIN ELEVATION.
13. EXISTING SLOPE IN STRUCTURE.
14. SLOPE WITH TAPERED INSULATION.
15. SUPPLY & INSTALL NEW PRE-MANUFACTURED ROOF EXPANSION JOINT.
16. SUPPLY & INSTALL NEW ROOF SYSTEM AS PER ROOF ASSEMBLIES, DETAILS, AND SPECIFICATIONS.
17. SUPPLY & INSTALL NEW PARAPET AT WALKWAY PERIMETER.
18. SUPPLY & INSTALL NEW ROOF CONTROL JOINT ALONG NEW ROOF AND EXISTING ADJACENT WALKWAY INTERFACE.
19. SUPPLY & INSTALL NEW FLASHING MEMBRANE AND SHEATHING AT ROOF / WALL INTERFACE.
20. SUPPLY & INSTALL NEW INSULATED CURB ALL ALONG NEW ROOF SYSTEM AND CONVENTION CENTRE CLADDING.
21. SUPPLY & INSTALL NEW PTAC UNIT WITHIN CURTAINWALL. REFER TO MECHANICAL. REFER TO DETAILS 3/S501 & 4/S506.
22. PROVIDE ANTI-SLIP TAPE TO DENOTE TEXTURE CHANGE. REFER TO SPECIFICATION.
23. SUPPLY & INSTALL 24 GA. 150MM X 75MM THROUGH-WALL OPEN PRE-FINISHED METAL SCUPPER AT NEW ROOF CONTROL JOINT WALL. BOTTOM OF SCUPPER TO BE 61MM ABOVE ROOF DRAIN ELEVATION.
24. EDGE OF EXISTING TILE.
25. PROVIDE WOOD BLOCKING AS REQUIRED FOR MOUNTING CONTINUOUS STAINLESS STEEL HANDRAILS.

1/A101 NORTH WALKWAY FLOOR PLAN
1:100

3/A101 NORTH WALKWAY PLAN DETAIL
1:10

1/A101 NORTH WALKWAY ROOF PLAN
1:100

Cibinel Architecture Ltd
560 ACADEMY ROAD WINNIPEG MB R3N 0E3
T. 204 989 8910

ARCHITECT

Winnipeg

CLIENT

NO.	DATE	REVISION / ISSUANCE
01	2021.05.05	ISSUED FOR CONSTRUCTION

Tender Package

Seal

PROVINCE OF MANITOBA — MICHAEL ACHT 2021-05-04 — REGISTERED ARCHITECT

PROVINCE OF MANITOBA — CIBINEL ARCHITECTURE LTD. No. 225 — APPROVED ARCHITECTURAL CORPORATION

MAA Digital Signature Applied

Project

CARLTON STREET WALKWAY UPGRADES

155 + 185 Carlton Street / Winnipeg, MB

Bid Opportunity No. 111-2020

Sheet Title

NORTH WALKWAY FLOOR + ROOF PLANS

Project No. 1943

Sheet A101

CIBINEL – Arch D – 24" X 36"