GENERAL NOTES

1. HATCHED AREAS ARE NOT IN ARCHITECTURAL SCOPE OF WORK. REFER TO STRUCTURAL, MECHANICAL, AND ELECTRICAL FOR WORK IN THESE AREAS. REFER TO MECHANICAL AND ELECTRICAL DRAWINGS FOR REVISIONS TO ANY MECHANICAL AND ELECTRICAL SERVICES AND DEVICES WITHIN AREAS OF NEW CONSTRUCTION.
2. PATCH, REPAIR, AND MAKE GOOD ANY INTERIOR OR EXTERIOR FINISH AFFECTED BY SCOPE OF DEMO, WORK, OR DAMAGE DURING CONSTRUCTION.
3. ALL EXPOSED STRUCTURAL STEEL, SUPPORT STRUCTURE, METAL DECK, STEEL FRAMING, DOOR FRAMES, WALLS, MECHANICAL & ELECTRICAL SERVICE LINES AND CONDUIT WITHIN WALKWAYS TO BE PAINTED.

KEYNOTES

1. LINE OF BUILDING FACE ABOVE.
2. SURFACE MOUNTED LINEAR LED DOWNLIGHT TYP. - REFER TO ELECTRICAL.
3. EXISTING CONCRETE BEAM
4. EXISTING SUSPENDED LINEAR METAL PANEL SOFFIT SYSTEM AND FASCIA TO BE REMOVED, MODIFIED, AND SALVAGED FOR REUSE AS REQUIRED TO FACILITATE WORK.
5. SURFACE MOUNTED SOFFIT LED DOWNLIGHT TYP. - REFER TO ELECTRICAL.
6. ALIGN VERTICAL FACE OF ALUMINUM CLOSURE WITH FACE OF EXISTING CONCRETE BEAM.

NORTH WALKWAY
REFLECTED CEILING PLAN
1:100

NORTH WALKWAY
SOFFIT PLAN
1:100

Cibinel Architecture Ltd
560 ACADEMY ROAD WINNIPEG MB R3N 0E3
T. 204 989 8910

ARCHITECT

CLIENT

NO.	DATE	REVISION / ISSUANCE
01	2021.05.05	ISSUED FOR CONSTRUCTION

Tender Package

Seal

PROVINCE OF MANITOBA MICHAEL ACHT 2021-05-04 REGISTERED ARCHITECT
PROVINCE OF MANITOBA CIBINEL ARCHITECTURE LTD. No. 225 APPROVED ARCHITECTURAL CORPORATION
MAA Digital Signature Applied

Project

CARLTON STREET WALKWAY UPGRADES
155 + 185 Carlton Street / Winnipeg, MB

Bid Opportunity No. 111-2020

Sheet Title

NORTH WALKWAY
RCP + SOFFIT PLAN

Project No. 1943

Sheet A103

CIBINEL – Arch D – 24" X 36"