GENERAL NOTES

1. HATCHED AREAS ARE NOT IN ARCHITECTURAL SCOPE OF WORK. REFER TO STRUCTURAL, MECHANICAL, AND ELECTRICAL FOR WORK IN THESE AREAS. REFER TO MECHANICAL AND ELECTRICAL DRAWINGS FOR REVISIONS TO ANY MECHANICAL AND ELECTRICAL SERVICES AND DEVICES WITHIN AREAS OF NEW CONSTRUCTION.
2. ALL EXPOSED STRUCTURAL STEEL, SUPPORT STRUCTURE, METAL DECK, STEEL FRAMING, DOOR FRAMES, WALLS, MECHANICAL & ELECTRICAL SERVICE LINES AND CONDUIT WITHIN WALKWAYS TO BE PAINTED.

KEYNOTES

1. EXISTING T/O FINISHED FLOOR.
2. ALIGN CURTAINWALL VERTICAL WITH CENTRELINE OF EXISTING COLUMN TYP.
3. SUPPLY & INSTALL NEW PTAC UNIT WITHIN CURTAINWALL. REFER TO MECHANICAL. REFER TO DETAILS 3/S501 & 4/S506.
4. EXISTING T/O STRUCTURAL STEEL.
5. ANGLE CURTAINWALL HORIZONTAL TO ALIGN WITH EXISTING FLOOR SLOPE.

1 A202 SOUTH WALKWAY NORTH ELEVATION
1:100

2 A202 SOUTH WALKWAY SOUTH ELEVATION
1:100

4 A202 SOUTH WALKWAY SECTION
1:100

3 A202 SOUTH WALKWAY SECTION
1:100

Cibinel Architecture Ltd
560 ACADEMY ROAD WINNIPEG MB R3N 0E3
T. 204 989 8910

ARCHITECT

Winnipeg

CLIENT

NO.	DATE	REVISION / ISSUANCE
01	2021.05.05	ISSUED FOR CONSTRUCTION

Tender Package

Seal

PROVINCE OF MANITOBA MICHAEL ACHT 2021-05-04 REGISTERED ARCHITECT
PROVINCE OF MANITOBA CIBINEL ARCHITECTURE LTD. No. 225 APPROVED ARCHITECTURAL CORPORATION
MAA Digital Signature Applied

Project

CARLTON STREET WALKWAY UPGRADES
155 + 185 Carlton Street / Winnipeg, MB

Bid Opportunity No. 111-2020

Sheet Title

SOUTH WALKWAY ELEVATIONS + SECTIONS

Project No. 1943

Sheet A202

CIBINEL – Arch D – 24" X 36"