



184-2020 ADDENDUM 1

LANDFILL GAS COLLECTION EXPANSION

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
TENDER**

ISSUED: April 9, 2020
BY: Irvin Slike
TELEPHONE NO. 204 806-0957

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE TENDER AND SHALL FORM A PART
OF THE CONTRACT DOCUMENTS**

Template Version: A20190115

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Tender, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid may render your Bid non-responsive.

QUESTIONS AND ANSWERS

- Q1: Is the Non-fused disconnect on the new air compressor container to be supplied by electrical? Or does this come pre-mounted on the new air compressor container.**
- A1: The non-fused disconnect on the outside of the new air compressor container is to be supplied and mounted by the air compressor vendor.
- Q2: Where is the heat trace on the condensate drain to be fed from?**
- A2: The heat trace from the condensate drain is to be fed from inside the new air compressor container. The air compressor vendor will need to ensure a breaker is available in their circuit breaker panel for this. It will need to be a single pole, 15A, GFCI breaker.
- Q3: Please confirm all programing calibration & setup of the instruments in the new air compressor container will be done by others.**
- A3: The additional monitoring devices are a pressure transmitter that does not require programming/calibration, and three temperature switches/thermostats that only require turning the dial to the proper setting. The contractor will be responsible for the setup of these devices at the new air compressor container. The City will supply the required temperature settings for the temperature switches and thermostats during the submittal phase of the project.