

NOTE:

1. SIZE OF CURB BOX TO SUIT SITE REQUIREMENTS

RE-INSTALL EXISTING HOOD

NEW DUCT EXTENSION

FILL VOIDS WITH BATT INSULATION

CURB CONSTRUCTION:

- 5/8" PLYWOOD ALL SIDES
- 2X3 BLOCKING TOP & BOTTOM
- RIGID INSULATION
- 2X4 STUDS @ 16" O.C.
- FASTEN BOTTOM PLATE TO DECK
- BATT INSULATION

SEAL NEW DUCT EXTENSION TO EXISTING DUCT

LAP & SEAL NEW VAPOUR BARRIER TO DUCT

SLOPE

12" MIN.

FIRE STOP WHERE REQUIRED

MOD BIT CAP SHEET

MOD BIT BASE SHEET

CONTINUOUS SBS AIR/VAPOUR BARRIER ADHERED TO DECK LAP & SEAL TO NEW CURB

EXISTING ROOF DECK

DECK SHEATHING

ROOF CURB @ DUCT DETAIL

<p>QCA Building Envelope Ltd. 1295 Pembina Highway Winnipeg, MB R3T 2B0 Tel: (204) 371-0996</p>	
<p>RIVER OSBORNE COMMUNITY CC 101 PEMBINA HWY, WPG, MB R3L 1Z3</p>	
<p>CITY OF WINNIPEG</p>	
Dwg. No.	265-2020_Drawing_A5-R0
Date	September 6, 2019 Scale N.T.S.
<p>This drawing is the property of QCA Building Envelope Ltd. It may not be reproduced without consent.</p>	