



NOTES:

1. ALL WORK AND MATERIALS TO BE IN ACCORDANCE WITH LATEST REVISION OF THE CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS.
2. LEGAL PLAN AND UNDERGROUND INFORMATION FROM CITY OF WINNIPEG LBIS. CONTRACTOR TO VERIFY ALL UNDERGROUNDS IN THE FIELD.
3. CONTRACTOR TO TAKE PRECAUTIONARY STEPS TO AVOID DAMAGE FROM CONSTRUCTION ACTIVITIES TO TREES WITHIN THE LIMITS OF CONSTRUCTION.
4. LOCATION OF EXISTING SERVICES TO CONFIRMED IN THE FIELD BY THE CONTRACTOR.
5. LIMITS OF BOULEVARD GRADING TO BE FINALIZED IN THE FIELD BY THE CONTRACT ADMINISTRATOR.
6. ADJUST ALL WATER VALVES, MANHOLES, CATCH BASINS AND CATCH PITS TO GRADE.
7. PAVEMENT REPAIRS SHOWN ARE ONLY REPRESENTATIVE APPROXIMATION OF TENDERED QUANTITIES.

LEGEND

- ASPHALT OVERLAY
- FULL DEPTH CONCRETE REPAIRS
- ASPHALT REPAIRS
- SPLASH STRIP REPAIRS
- CROSS STITCH REPAIRS
- CURB REPAIRS
- CONCRETE PAVEMENT PRESERVATION

METRIC

WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

APEGM
Certificate of Authorization
Dillon Consulting Limited (MB)
Date: 2020/04/24

B.M.
ELEV.

NO.	REVISIONS	DATE	BY
2	ISSUED FOR TENDER	20/04/24	TJP
1	ISSUED FOR 90% REVIEW	20/04/17	TJP

DESIGNED BY	TJH
DRAWN BY	TJH
CHECKED BY	KP
APPROVED BY	TJP
HOR. SCALE	1:500
VERTICAL	—
DATE	

DILLON CONSULTING

RELEASED FOR CONSTRUCTION

DATE

ENGINEER'S SEAL

CONSULTANT PROJECT NUMBER
20-2590

Winnipeg

THE CITY OF WINNIPEG
PUBLIC WORKS DEPARTMENT

2020 STREET MAINTENANCE PROGRAM

NORTHBOUND BROOKSIDE BOULEVARD
INKSTER BOULEVARD TO MOLLARD ROAD

CONCRETE - STA. 2+440 TO STA. 2+820

CITY DRAWING NUMBER
SHEET 05 OF 37
TENDER NO. 289-2020

c:\projectwise\working directory\projects 2020\40tjh\dms20622\202590-CT-CON-Brookside.dwg