

Appendix A - Host Pipe Conditions and Inspections

Sewer Details																								Required Inspections																
DWG	Sheet	Sewer Asset	Street Name	Location	Manholes				Length	Size		Shape	Flow Type	Material	Sewer Services	Patching for Close-Fit Liners			Intruding Connections		Removal of Roots and Grease		Solid Debris / Other			Sewer Service Grouting - Man Entry for Sewers >900mm		Pre Repair	Pre & Post Design	Pre Lining	Post Lining	Warranty								
					Upstream	Depth	Downstream	Depth		Height	Width					Patch <=1m	Patch >=1m	Description	# Intrad Conn	Description	Roots and Grease	Description	1st 3m	Qty >3m (m)	Qty at Joints	Description	Service Grouting						Description							
12592	1	S-MA20016321	BANNATYNE AV	MH AT RORIE ST TO 1ST MH E OF RORIE ST	S-MH20014669	6.82	S-MH20014701	6.16	91.5	1500	-	CIRCULAR	COMBINED	BRICK	17			1	TBI 62.08 m @ 9	1.0	NBL 32.70m US @ 12, RMB/RML 18.3m to 23.56 m @ 4, RMB/RML 24.68m to 31.37m @ 4, RML 54.06m @ 3, RMB 52.92 m to 57.30 m @5, RFB 64.07 m to @ 2 to 5, DAGS 64.8 m to 66.4m @7 to 8, RTC 65.7m @11	1.0	3	DAE 33.2 m 4 to 5, DAE 35.8m 4 to 5, DAE 46.13m @ 9							YES	YES	YES	YES						
12593	2	S-MA20018612	BANNATYNE AV	MH AT FURBY ST (CL) TO MH AT LYDIA ST	S-MH20016671	5.77	S-MH20016698	6.02	101.0	1500	1000	EGG	COMBINED	BRICK	23		4	TBI 13.56 m @ 1, TBI 13.75m @ 11, TBI 44 m from US end @ 3, TBI 46 m from US end @ 9				1.0	6	DAE 7.9 m from US end (reversal) 7 to 10, DAE 13.9m from US end @7 to 11, DAE 32.7 m from US end @ 6 to 9, DAE 46 m from US end @ 7 to 9, SAE 46.65 m from us end @ 3 to 6, DAE 73.75 m from US end @ 9 to 8										YES	YES	YES	YES			
12594	3	S-MA20019010	LOGAN AV	MH AT LAURA ST TO MH AT ELLEN ST (W PL)	S-MH20017056	5.77	S-MH20017058	5.85	80.1	1500	1000	EGG	COMBINED	BRICK	22	1	3.3	MMS 37.2-41.5 m DS	1	TBI 37.3 m DS @ 2			1	11	DAE 6.7 m DS @ 2 to 5, DAE 18.4 m DS @ 3 to 6, DAE 35.06 m DS @ 3 to 6, DAE 37.20m DS @ 9 to 10, DAE 39.3 m DS @ 3 to 4, DAE 40.6m DS @ 8 to 9, DAR 40.6 m DS @ 11, DAE 40.4 m DS @ 3 to 4, DAE 45.7m DS @ 7 to 9, DAE 45.8m DS @ 3, DAE 50.53 m DS @ 2										YES	YES	YES	YES		
12595	4	S-MA50004336	METCALFE AV	2ND MH W OF ST MARYS RD TO METCALFE FPS	S-MH50003713	8.58	S-MH50003719	8.22	4.6	1700	1100	EGG	COMBINED	CONCRETE	0	1	2.0	ESTIMATED QUANTITIES SSS 0.0-3.5m DS @ 3-9; SSS 7.9-15.0 m DS @ 4-8; SSS 20.0-20.8m DS @ 4-5; SSS 22.4-23.5m DS @ 7-9; SSS 30.3-31.5m DS @ 7-8; HSV 32.2m @ 3-5;																	YES	YES	YES	YES	YES	
12595	4	S-MA50004316	METCALFE AV	1ST MH W OF ST MARYS RD TO 2ND MH W OF ST MARYS RD	S-MH50003712	8.21	S-MH50003713	8.52	34.2	1700	1100	EGG	COMBINED	CONCRETE	7	1	13.7	SSS 0.0-8.0M DS @ 5-7; SSS 92.3-92.9 @ 4-8																			YES	YES	YES	YES
12595	4	S-MA50004315	METCALFE AV	MH AT ST MARYS RD (CL) TO 1ST MH W OF ST MARYS RD	S-MH50003550	8.03	S-MH50003712	8.21	92.9	1700	1100	EGG	COMBINED	CONCRETE	9	1	7.6	SSS 16.2-17.2M DS @ 4-6; SRI 24.8-27.5M DS @ 6-9; SSS 76.2-83.4M DS @ 5-7					1	2	-DAE 7.6m DS @ 12, DAE 15.2 m DS @ 6 to 11, DAE/DSC/DAGS from 69.6 m DS to 72 m from 5 to 7											YES	YES	YES	YES	
12596	5	S-MA70003174	ST MARYS RD (CL)	MH AT CARRIERE AV TO MH AT METCALF AV	S-MH50006483	8.08	S-MH50003550	8.03	82.8	1700	1100	EGG	COMBINED	CONCRETE	14	1	9.9	SSS 16.2-17.2M DS @ 4-6; SRI 24.8-27.5M DS @ 6-9; SSS 76.2-83.4M DS @ 5-7					1	1.4	4	-DAE 7.4 m DS @ 3 to 4 from service not at joint, DAE 16.2 m DS at service not joint @ 1 to 5, DAE 25.6 m DS to 30m DS at 7, DAE 46.4 m DS @ 12 service not joint, DAE 57.4m DS @ 1 to 2											YES	YES	YES	YES