REGENT AVE W

INSTALL CB RISER & REPLACE FRAME
(AP-011) AND COVER (AP-012)

INSTALL CB RISER

REPLACE FRAME
(TF100 OR AP-006)
AND COVER (AP-008)

CB PLUGGED

1+650

1+600

1+550

1+500

1500

300 AC WM

1200 WWS

1200 WWS

600 WWS

100 GAS

100 GAS

600 WWS

1200 WWS

200 GAS

300 AC WM
200 GAS
HYDRO 25 kV
HYDRO 25 kV

1496

1950 LDS

300 AC WWS

1950 LDS

1950 LDS

600 WWS

1200 WWS

MATCHLINE AT STA: 1+480

MATCHLINE AT STA: 1+680

NOTES:
1. ALL WORK AND MATERIALS TO BE IN ACCORDANCE WITH LATEST REVISION OF THE CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS.
2. LEGAL PLAN AND UNDERGROUND INFORMATION FROM CITY OF WINNIPEG LBIS. CONTRACTOR TO VERIFY ALL UNDERGROUNDS IN THE FIELD.

3. CONTRACTOR TO TAKE PRECAUTIONARY STEPS TO AVOID DAMAGE FROM CONSTRUCTION ACTIVITIES TO TREES WITHIN THE LIMITS OF CONSTRUCTION.
4. LOCATION OF EXISTING SERVICES TO BE CONFIRMED IN THE FIELD BY THE CONTRACTOR.
5. LIMITS OF BOULEVARD GRADING TO BE FINALIZED IN THE FIELD

BY THE CONTRACT ADMINISTRATOR.
6. ADJUST ALL WATER VALVES, MANHOLES, CATCH BASINS AND CATCH PITS TO GRADE.
7. PAVEMENT REPAIRS SHOWN ARE ONLY REPRESENTATIVE OF APPROXIMATION OF TENDERED QUANTITIES.
8. WHERE THE CONTRACT ADMINISTRATOR DIRECTS CONCRETE

RISERS ARE TO BE INSTALLED, THE CONTRACTOR SHALL REMOVE THE EXISTING FLAT TOP REDUCER, PLACE RISERS AS DIRECTED BY THE CONTRACT ADMINISTRATOR, AND REINSTALL THE EXISTING FLAT TOP REDUCER.

**PRELIMINARY ONLY
NOT FOR CONSTRUCTION**

LEGEND

	ASPHALT OVERLAY			CROSS STITCH REPAIRS
	FULL DEPTH CONCRETE REPAIRS			CURB REPAIRS
	SIDEWALK REPAIRS			

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

APEGM
Certificate of Authorization
Dillon Consulting Limited (MB)
No. 1789   Date: 2020/--/--

B.M. ELEV.	
DESIGNED BY	MF
DRAWN BY	PMW
CHECKED BY	KP
APPROVED BY	TJP
HOR. SCALE	1:500
VERTICAL	—

DILLON CONSULTING

ENGINEER'S SEAL

RELEASED FOR CONSTRUCTION

CONSULTANT PROJECT NUMBER
20-2914

NO.	REVISIONS	DATE	BY
2	ISSUED TO MATERIALS MANAGEMENT	20/07/29	TJP
1	ISSUED FOR 90% CITY REVIEW	20/07/10	TJP

DATE

Winnipeg

THE CITY OF WINNIPEG
PUBLIC WORKS DEPARTMENT

2020 STREET MAINTENANCE PROGRAM
REGENT AVE W
ROUGEAU AVE TO PLESSIS RD
ASPHALT OVERLAY - STA: 1+480 TO STA: 1+680

CITY DRAWING NUMBER	
SHEET NO.	07 OF 12
TENDER NO.	471-2020

D:_202914\Files From PW\202914-CT-CON-REG.dwg