

NOTE: CHAINAGES SHOWN ARE ALONG CENTRE LINE OF ROW



NOTE: VALVES TO BE INSTALLED COUNTER-CLOCKWISE TO CLOSE

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

0.0 5.0 10.0 15.0 20.0 25.0

CONSTRUCTION NOTES:
1. EXPOSE EXISTING WATERMAIN & CONFIRM INVERTS PRIOR TO CONSTRUCTION.
2. LOCATION OF ALL SERVICES TO BE CONFIRMED IN THE FIELD.
3. INSTALL WATERMAIN BY TRENCHLESS METHODS.
4. TRENCHES AND EXCAVATIONS WITHIN 1.0m OF A PAVED AREA INCLUDING SIDEWALKS SHALL BE CLASS 3 BACKFILL.
5. ALL MATERIALS SHALL CONFORM TO THE CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS.
6. MINIMUM COVER TO TOP OF WATERMAIN SHALL BE 2.4m.
7. REPLACE ALL EXISTING LEAD SERVICES FROM PROPOSED WATERMAIN TO P/L.
8. NOTIFY ALL AFFECTED RESIDENTS AND BUSINESSES 24 HOURS IN ADVANCE OF ANY WATER SHUTDOWNS OR DISRUPTION OF SERVICE.

WATER SERVICE INFORMATION

ADDRESS	PIPE SIZE & MATERIAL (STREET)	PIPE SIZE & MATERIAL (PROP.)	SHORT & LONG MEASUREMENT	CORP. LOCATION	REMARKS
880 SCOTLAND AVE	150	150	–	28 E OF MLV	OUTSIDE LIMITS
RESIDENTIAL	PVC	PVC	–		
395 STAFFORD ST	25	25	3 W/WHL	3 E/SC	OUTSIDE LIMITS
COMMERCIAL	CU	CU	82 WWL STAFFORD	OPP S/C	
401 STAFFORD ST	20	20	3.7 E/WBL		OUTSIDE LIMITS
COMMERCIAL	CU	CU	–		
402 STAFFORD ST	20	20	41 W/WHL	19 EEL STAFFORD	OUTSIDE LIMITS
COMMERCIAL	CU	CU	17.5 EEL STAFFORD		
909 LORETTE AVE	20	20	8.2 W/E BLDG	OPP C/S	OUTSIDE LIMITS
COMMERCIAL	CU	CU	9.1 W/E LL		

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
Stantec Consulting Ltd.
No. 1301

EXISTING	LEGEND-PLAN	PROPOSED	EXISTING	LEGEND-PLAN	PROPOSED	EXISTING	LEGEND-PROFILE	PROPOSED
150 WM	WATERMAIN	150 WM		HYDRO			℄ PROFILE	
	HYDRANT			M.T.S.			NORTH OR WEST GUTTER	
	VALVE			CONCRETE			SOUTH OR EAST GUTTER	
300 LDS	LAND DRAINAGE SEWER	300 LDS		ASPHALT			NORTH MEDIAN GUTTER	
250 WWS	WASTE WATER SEWER	250 WWS		SIDEWALK			SOUTH MEDIAN GUTTER	
	MANHOLE			ASPHALT MILL & FILL			NORTH OR WEST P/L	
	CATCH BASIN			STREET LIGHT			SOUTH OR EAST P/L	
	CURB INLET/CATCH PIT			HYDRO POLE				
	TRANSIT STOP			SURVEY BAR				
	GAS		(31.334)	ELEVATION	(32.231)			
	PROPERTY LINE			SIDEWALK RAMP				

LOCATION APPROVED
UNDERGROUND STRUCTURES

SUPV. U/G STRUCTURES COMMITTEE DATE

NOTE:
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

B.M.
ELEV.

NO.	REVISIONS	DATE	BY
0	ISSUED FOR TENDER	22.01.06	K.W.R.

Stantec
500 - 311 Portage Avenue, Winnipeg MB Canada
www.stantec.com

DESIGNED BY	D.L.	CHECKED BY	D.L.
DRAWN BY	O.S.	APPROVED BY	R.S.
HOR. SCALE:	1:250	RELEASED FOR CONSTRUCTION:	
VERTICAL:	1:50		
DATE	2021/09/28	DATE	Jan 4/22

ENGINEER STAMP
PROVINCE OF MANITOBA
R. M. SHERLOCK
Member
24045
REGISTERED PROFESSIONAL ENGINEER
Jan 4/22

CONSULTANT DRAWING N0.
U-204

Winnipeg
THE CITY OF WINNIPEG
PUBLIC WORKS DEPARTMENT
ENGINEERING DIVISION

2019-2023 STAFFORD/TAYLOR/CORYDON
TENDER 2
STAFFORD STREET
STA 3+710 TO STA 3+835
UNDERGROUND INFRASTRUCTURE - WM RENEWAL

SHEET 37 OF 53
CAD FILE DRAWING NUMBER 08020u-201.dwg
CITY DRAWING NUMBER P-3526-27

\\N11370620\1000_drawing\08020_sheet_files\02_civil\Tender2\08020u-201.dwg
2021/01/06 8:12 AM, by: rbenner, Sheet: U-204