



483-2021 ADDENDUM 4

2021-2023 REGIONAL PAVEMENT RENEWAL: JUBILEE AVENUE AND PEMBINA HIGHWAY

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID/PROPOSAL

ISSUED: January 24, 2022
BY: David Wiebe, P.Eng., LEED AP, PTOE
TELEPHONE NO. 204 453-2301

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID/PROPOSAL AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: Add 2021-03-05

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

PART B – BIDDING PROCEDURES

Revise: B2.1 to read:

The Submission Deadline is 12:00 noon Winnipeg time, January 27, 2022.

FORM B: PRICES

Replace: 483-2021 Addendum_3-Form_B: Prices with 483-2021 Addendum_4-Form_B: Prices. The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

Form B(R2):

Revise: Items C.3 i), C.4 i), D.3 i), D.4 i), I.6, I.7, J.4, J.5, J.6, J.7

Page numbering on some forms may be changed as a result.

PART E – SPECIFICATIONS

Revise: E59.41.15 to read:

E59.41.15 Installation of Overhead Span of #4 Duplex Between New or Existing Streetlight Poles and Connect Luminaire to Provide Temporary Overhead Feed.

- (a) This pay item will be measured on linear metre basis and paid for at the Contract Unit Price per linear metre for "Installation of Overhead Span of #4 duplex Between New or Existing Streetlight Poles and Connect Luminaire to Provide Temporary Overhead Feed". The number of metres to be paid for at the Contract Unit Price shall be verified and accepted by Manitoba Hydro. The Price shall be payment in full for performing all operations herein described including attachment of the #4 duplex overhead conductor using a perform grip (c/w spool insulator(s) to davit arm if necessary), sagging conductor, connection of luminaire using 2C#12 copper conductor and all other items incidental to the Work included in the Specification.

Revise: E59.41.16 to read:

E59.41.16 Removal of Overhead Span of #4 Duplex Between New or Existing Streetlight Poles to Remove Temporary Overhead Feed.

- (a) This pay item will be measured on a linear metre basis and paid for at the Contract Unit Price per lineal metre for "Removal of Overhead Span of #4 duplex Between New or Existing Streetlight Poles to Remove Temporary Overhead Feed". The number of metres to be paid for at the Contract Unit Price shall be verified and accepted by Manitoba Hydro. The Price shall be payment in full for performing all operations herein described including removal of the #4 duplex overhead conductor, spool insulator(s) and all other items incidental to the Work included in the Specification.

DRAWINGS

Replace: 483-2021 _Drawing_P-3550-51-R0 with 483-2021 _Addendum_4-Drawing_P-3550-51-R1