

644-2021 ADDENDUM 2

ESPLANADE RIEL PEDESTRIAN BRIDGE CABLE STAY AND PYLON LIGHTING UPGRADES

URGENT

**PLEASE FORWARD THIS DOCUMENT TO
WHOEVER IS IN POSSESSION OF THE
BID/PROPOSAL**

ISSUED: February 8, 2022
BY: Darren Burmey, P.Eng., FEC
TELEPHONE NO. 204 986-5409

**THIS ADDENDUM SHALL BE INCORPORATED
INTO THE BID/PROPOSAL AND SHALL FORM
A PART OF THE CONTRACT DOCUMENTS**

Template Version: Add 2021-03-05

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

PART D – SUPPLEMENTAL CONDITIONS

- Revise D5.4 to read: There are many lights on the bridge. The ones to be upgrades are the cable stay and pylon lights. There are 9 sets of 2 cable stays on each of the east and west spans (36 total). There are 7 cable stays around the centre plaza. Each cable stay has a light illuminating the cable (43 lights total). There are two lights on the bridge deck at the pylon location that illuminates the pylon. There are also **8 lights on the centre plaza roof** that illuminates the pylon and there are 2 lights on the west river pier of Provencher Bridge that illuminates the pylon. It is desired that up to **55 lights** be upgraded. Upgrading of the 2 lights on the west river pier of Provencher Bridge is desired but it may not be cost effective to have it colour controlled.'
- Revise D7.3 to read: The main spans cable stay lights (36), centre plaza cable stay lights (7), **centre plaza roof lights (8)**, and bridge deck lights (2) are to be upgraded to LED with a control to create coloured visual effects that can be customized for special days. The lights on the west river pier of the Provencher Bridge (2) are to be upgraded to LED but do not need to be colour controlled. The photocell that turns on and off the lights is to be replaced.