



807-2021 ADDENDUM 1

2021-2022 PIONEER AVENUE, WILLIAM STEPHENSON WAY, COLONY STREET AND ST. MARY AVENUE RENEWALS PROJECT

ISSUED: March 11, 2022
BY: Scott Suderman, C.E.T., P.Eng.
TELEPHONE NO. 204 782-7189

URGENT

PLEASE FORWARD THIS DOCUMENT TO WHOEVER IS IN POSSESSION OF THE BID/PROPOSAL

THIS ADDENDUM SHALL BE INCORPORATED INTO THE BID/PROPOSAL AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS

Template Version: Add 2021-03-05

Please note the following and attached changes, corrections, additions, deletions, information and/or instructions in connection with the Bid/Proposal, and be governed accordingly. Failure to acknowledge receipt of this Addendum in Paragraph 10 of Form A: Bid/Proposal may render your Bid/Proposal non-responsive.

FORM B: PRICES

Replace: 807-2021 Form B: Prices with 807-2021 Addendum 1 - Form B: Prices.

The following is a summary of changes incorporated in the replacement Bid/Proposal Submission:

- Form B(R1): Changed titles for Section A and Section B from Concrete Reconstruction to Asphalt Reconstruction
- Form B(R1): Add Items A.10, A.11 ii) A.18 i), A.18 ii) d). A.18 iii), A.19, A.21 related to the pavement restorations on Main Street for the Traffic Signals installation at Pioneer Avenue
- Form B(R1): Increased quantities for Items A.11, A.12, A.20 related to the pavement restorations on Main Street for the Traffic Signals installation at Pioneer Avenue
- Form B(R1): Changed description of all Installation of Conduits to remove the word "open trench"
- Form B(R1): Added Section I related to the watermain renewal on Spence Street within the construction limits.

Page numbering on some forms may be changed as a result.

PART D – SUPPLEMENTAL CONDITIONS

- Add: D2.5 (a) (xxi) Watermain Renewal on Spence Street.
- Revise: D20.1 to read: The Contractor shall achieve Substantial Performance within *seventy-five (75)* consecutive Working Days of the Commencement of Work as specified in D15.
- Revise: D21.2 to read: The Contractor shall achieve Total Performance within *eighty (80)* consecutive Working Days of the Commencement of Work as specified in D15.

PART E – SPECIFICATIONS

- Add: E8.5 (d) Pedestrians are to be maintained on both sides of Main Street at all times. One lane closure is permitted in the northbound and southbound directions. An additional lane in northbound and southbound directions are permitted in off-peak rush hours to accommodate the installation of the traffic signals works. Temporary pedestrian paths of travel may be set up on the street if necessary. This work is preferred to be executed in July as there are no planned special events. The Contractor is required to maintain the temporary Transit stop location during this work on the west side of Main Street.

Add: E8.6 (f) Private access is to be maintained at all times.

Add: E37 Water Main Works

E37. WATER MAIN WORKS

E37.1 Provisional Items

E37.1.1 The Provisional Items listed in the Form B Prices are part of the Contract.

E37.1.2 The Contractor shall not perform Work included in Provisional Items without prior authorization from the Contract Administrator. All work included in the Provisional Items will be carried out within the construction areas shown on the Drawings.

E37.1.3 Notwithstanding C7, the City reserves the right to diminish all or any portion of the Items of Work listed in the Provisional Items and no claim shall be made for damages on grounds of loss of anticipated profit or for any other reason.

E37.2 Temporary Surface Restorations

- (a) Further to clause 3.3 of CW 1130, the Contractor shall temporarily restore surfaces within the limits of the St Mary Avenue road reconstruction as follows:
- (b) Backfill and level boulevards and grassed areas to match existing surface elevations;
- (c) Cap excavations in street pavement with a 150 mm thick layer of "Concrete for Temporary Restoration of Utility Pavement Cuts" as specified in CW 3310;
- (d) Cap excavations in sidewalk pavement with 50 mm thick layer of "Concrete for Temporary Restoration of Utility Pavement Cuts" as specified in CW 3310;
- (e) Insulate temporary concrete where required during 24hr curing period;
- (f) Where curb has been removed as part of the pavement cut pour temporary curb using "Concrete for Temporary Restoration of Utility Pavement Cuts" as specified in CW 3310.
- (g) Remove all temporary pavements prior to permanent restorations.

E37.2.1 The Contractor shall monitor and maintain temporarily restored surfaces as required until permanent restoration is complete.

E37.2.2 If, in the opinion of the Contract Administrator, temporarily restored surfaces are not being adequately maintained or were not properly constructed and pose a danger to the public, maintenance or reconstruction will be done by the City forces with no advance notification the Contractor.

E37.2.3 All costs associated with the maintenance or reconstruction of temporary pavement incurred by the City shall be deducted from future payments to the Contractor.

E37.2.4 Temporary surface restorations shall be measured on an area basis and paid for at the contract unit price for "Temporary Surface Restorations", "a) street pavement" or "b) sidewalk". The area to be paid for shall be the total number of square metres of street pavement or sidewalk temporarily restored, accepted and measured by the Contract Administrator.

E37.2.5 No measurement or payment will be made for the temporary restoration of barrier or lip curb.

E37.2.6 No measurement or payment will be made for the temporary restorations of boulevards and grassed areas.

E37.2.7 No measurement or payment will be made for the removal of temporary pavement prior to permanent restoration.

DRAWINGS

Add: 807-2021_Drawing_ S-1667

807-2021_Drawing_221-02275-00-01-RB

807-2021_Drawing_221-02275-00-02-RB