

MAIN FLOOR PLAN

1 A101 1:100

GENERAL NOTES

1. ALL INTERIOR WALLS TO EXTEND TO U/S OF STRUCTURE UNLESS OTHERWISE NOTED.
2. ALL DIMENSIONS SHOWN TO FACE OF FINISH UNLESS OTHERWISE NOTED.
3. PROVIDE 19MM PLYWOOD BACKERBOARD AT WALL MOUNTED ELECTRICAL EQUIPMENT
4. COORDINATE MECHANICAL AND ELECTRICAL WITH STRUCTURE AND ADJUST FURRING AS REQUIRED IN CONJUNCTION WITH ARCHITECT.
5. ALL INTERIOR WALLS TO BE W5 UNLESS OTHERWISE NOTED. REFER TO ENLARGED PLANS AND STAIR DETAILS FOR ADDITIONAL WALL TAGS.
6. REFER TO SLAB PLAN FOR ADDITIONAL LOCATIONS OF SLOPED CONCRETE FLOORS.
7. HATCH DENOTES CONCRETE WALL
8. HATCH DENOTES CONCRETE MASONRY WALL
9. STEEL STUD HEADER REQUIRED AT ALL INTERIOR CURTAINWALL. COORDINATE PERFORMANCE REQUIREMENTS WITH SPECIFICATION.
10. REFER TO EXTERIOR ELEVATIONS FOR LOCATIONS AND EXTENT OF GLAZING.
11. FURNITURE SHOWN FOR COORDINATION PURPOSES ONLY.
12. COLUMNS, BEAMS AND CROSS BRACING SUPPORTING THE MAIN FLOOR REQUIRE A 45 MIN FIRE RESISTANCE RATING. FIRE RESISTANCE RATING TO BE ACHIEVED WITH CEMENTITIOUS FIREPROOFING UNLESS OTHERWISE NOTED.
13. ALL ELECTRICAL CONDUIT TO BE CONCEALED WITHIN CONCRETE MASONRY WALL

KEYED NOTES

1. EMERGENCY EYEWASH STATION. CENTRE BETWEEN DOORS
2. METAL GRATE AND RECESSED PIT FOR HOSE WASH
3. FIREFIGHTER'S POLE C/W LANDING MAT
4. FIRE DEPARTMENT CONNECTION - REFER TO MECHANICAL
5. WATER MAIN
6. HOSEBIB
7. RECESSED LINEAR TRENCH DRAIN
8. MASONRY WALL BELOW GLAZING TO BE W1. REFER TO DETAILS
9. LINE OF METAL PLATFORM ABOVE
10. MILLWORK
11. STAINLESS STEEL COUNTER C/W INTEGRAL SINK AND STAINLESS STEEL SHELF ABOVE
12. BOLLARD - TYP.
13. WEEPING TILE SUMP PIT
14. DOOR GUARD
15. INTUMESCENT FIRE PROTECTION AT COLUMN TO ACHIEVE 45MIN FRR
16. SPRINKLERED GLASS
17. FIRE RATED GLAZED
18. OPENING IN FLOOR ASSEMBLY ABOVE
19. WALL MOUNTED BICYCLE STORAGE RACK (4). PROVIDE PLYWOOD BACKING BEHIND WALL ASSEMBLY FOR MOUNTING. REFER TO ELEVATIONS
20. FIRE RATED GLAZED ENTRANCE SYSTEM. ALIGN WITH WALL AS SHOWN
21. BOTTLE FILLING STATION C/W COMPRESSOR AND SHELVING
22. HEIGHT ADJUSTABLE TOOL BENCH - OFF THE SHELF PRODUCT
23. ENTRANCE SLAB. REFER TO FOUNDATION PLAN FOR DIMENSIONS
24. PROVIDE DEPRESSION IN FLOOR TO ACCOMMODATE TILE FINISH.
25. OIL INTERCEPTOR. REFER TO FOUNDATION PLAN FOR LOCATION. COORDINATE WITH MECH.
26. GREASE INTERCEPTOR. REFER TO FOUNDATION PLAN FOR LOCATION. COORDINATE WITH MECH.
27. WATER CONNECTION FOR TRUCK WATER FILLING.
28. DOOR CONTROLS - REFER TO ELECTRICAL
29. 915MM X 915MM BODY ENTRY ACCESS HATCH LOCATED AT LOW LEVEL BEHIND DOOR SWING
30. WALL HYDRANT - REFER TO MECHANICAL
31. WATER METER - REFER TO MECHANICAL. APPROXIMATE LOCATION TO BE CONFIRMED BY ARCHITECT PRIOR TO INSTALLATION
32. CONCRETE CURB - REFER TO SLAB PLAN
33. SOUND CONTROL WINDOW ASSEMBLY
34. GEAR LOCKERS. PROVIDE BLOCKING AS REQUIRED FOR MOUNTING.
35. WARDROBE LOCKERS
36. PAINTED MARKINGS. COORDINATE WITH EXTERIOR LAYOUT
37. LINE OF CANOPY ABOVE
38. DEVICE MOUNTING BOLLARD
39. ENTRANCE MATTING
40. PROVIDE FURRING AS REQUIRED TO MEET WALL ALIGNMENT SHOWN . REFER TO DETAIL
41. ALIGN
42. CENTRE WALL ON GRIDLINE
43. WHITEBOARD. REFER TO INTERIOR ELEVATIONS
44. TACKBOARD. REFER TO INTERIOR ELEVATIONS
45. STORAGE RACKING FOR CASCADE SYSTEM. NIC.
46. HOSE - NIC.
47. METAL STORAGE SHELVING
48. GYPSUM TO WRAP AROUND CEMENTITIOUS COLUMN
49. HOUSEKEEPING PAD. COORDINATE SIZE WITH MANUFACTURER'S REQUIREMENTS
50. ACCESS PANEL
51. FULL HEIGHT GLAZING ALONG ACCESSIBLE ROUTE REQUIRES WARNING DECALS - REFER TO INTERIOR ELEVATIONS.
52. DOOR GUARD - REFER TO DETAILS

Cibinel Architecture Ltd

560 ACADEMY ROAD WINNIPEG MB R3N 0E3
T. 204 989 8910

ARCHITECT

NO.	DATE	REVISION / ISSUANCE
00	2023.02.03	ISSUED FOR CONSTRUCTION

Seal



Project

WFPS STATION 9

1083 AUTUMNWOOD DRIVE

Sheet Title

MAIN FLOOR PLAN

Project No. 2150

Sheet A101