

SLAB PLAN

1 / A100 — 1:100

GENERAL NOTES

1. GRADE BEAMS HAVE BEEN OFFSET FROM GRID LINES AS NOTED. REFER TO STRUCTURAL AND ARCHITECTURAL DETAILS.
2. REFER TO MAIN FLOOR PLAN FOR ADDITIONAL LOCATIONS OF SLOPED CONCRETE FLOORS.
3. HATCH DENOTES CONCRETE WALL ABOVE
4. HATCH DENOTES CONCRETE MASONRY WALL ABOVE
5. ALL GRADE BEAMS TO BE FW1
6. REFER TO DETAIL 6/A510 FOR PENETRATION DETAIL THROUGH MAIN FLOOR SLAB

KEYED NOTES

1. FUTURE LOCATION OF GEAR EXTRACTOR
2. NOT USED
3. SUMP PIT CONNECTED TO WEEPING TILE - REFER TO STRUCT & MECH.
4. WALL OF OPENINGS TO ALIGN
5. FIREPOLE. PROVIDE DEPRESSION IN CONCRETE FOR LANDING MAT. COORDINATE WITH MANUFACTURER'S REQUIREMENTS.
6. SLAB ON GRADE ABOVE COMPLETE WITH TRENCH DRAIN. SLOPE T.O SLAB TO DRAIN - REFER TO 1/A509, STRUCT., & MECH.
7. PERFORATED PERIMETER WEEPING TILE SLOPED 2% MIN TO SUMP PIT BELOW SLAB.
8. NON-PERFORATED WEEPING TILE SLOPED 2% MIN. TO SUMP PIT BELOW SLAB
9. CONNECTION OF PERFORATED DRAIN TILE TO NON-PERFORATED DRAIN TILE
10. DEPRESS SLAB TOPPING BELOW BOTH PUBLIC WASHROOMS TO ACCOMODATE TILE FLOORING. FINIAL FLOOR ELEVATION WITH FINISH FLOORING SHOULD ALIGN WITH ELEVATION OF CORRIDOR FINISH FLOORING. SHIM WALL DIVIDING WASHROOMS TO MATCH HEIGHT OF TYP. INTERIOR WALLS .COORDINATE WITH MAIN FLOOR PLAN FOR EXTENTS.
11. CONCRETE ENTRY SLAB
12. SUMP PIT DISCHARGE PIPE TO PENETRATE GRADE BEAM C/W PREFIN METAL ESCUTCHEON PLATE - REFER TO ELEVATIONS, STRUCT., & MECH.
13. CMU WALL CENTRED ON GRIDLINE AS SHOWN
14. LINE OF MASONRY WALL ABOVE.
15. HOUSEKEEPING PAD. COORDINATE SIZE WITH MANUFACTURER'S REQUIREMENTS
16. COORDINATE NEW SITE SERVICE LINES WITH BULIDING STRUCTURE. SERVICE LINE TO RUN UNDERNEATH GRADE BEAM - REFER TO MECH AND CIVIL FOR LOCATION.
17. 203 DIA. BOLLARDS - REFER TO STRUCTURAL.
18. GREASE INTERCEPTOR - REFER TO MECHANICAL. CENTRE WITH OIL INTERCEPTOR AS SHOWN.
19. OIL INTERCEPTOR - REFER TO MECHANICAL. CENTRE WITH GREASE INTERCEPTOR AS SHOWN.
20. 50MM HIGH CONCRETE CURB BELOW STUD WALL ASSEMBLY . CURB IS REQUIRED TO MEET HAZARDOUS MATERIAL CLASSIFICATION. REFER TO ELEC.
21. NOT USED.
22. WWS TIE IN TO BUILDING - REFER TO CIVIL
23. PAINTED MARKINGS. COORDINATE WITH EXTERIOR LAYOUT
24. PROVIDE CONTROL JOINT AROUND BOLLARDS AS SHOWN. PROVIDE SAW CUT IN CONCRETE AS SHOWN.
25. HOSE WASH PIT ACCESS LADDER TO BE MOUNTED TO SIDE OF CONCRETE PIT
26. CONCRETE CURB BELOW GLAZING. ALIGN EXTENTS WITH CURTAINWALL ASSEMBLY. REFER TO DETAILS
27. FLAT AREA TO MOUNT POSTS FOR GEAR LOCKERS. COORDINATE WITH MANUFACTURER'S REQUIREMENTS.
28. REFER TO ENLARGED PLANS FOR LOCATION OF DOORS IN CONCRETE MASONRY WALL.

Cibinel Architecture Ltd
560 ACADEMY ROAD WINNIPEG MB R3N 0E3
T. 204 989 8910

ARCHITECT

NO.	DATE	REVISION / ISSUANCE
00	2023.02.03	ISSUED FOR CONSTRUCTION

Seal



Project

WFPS STATION 9

1083 AUTUMNWOOD DRIVE

Sheet Title

SLAB PLAN

Project No. 2150

Sheet A100

CIBINEL - Arch D - 24" X 36"