1 REF.2 DETAIL
SCALE: 1:10

3 REF.2 DETAIL
SCALE: 1:10

5 REF.2 DETAIL
SCALE: 1:10

A REF.1 SECTION @ LOUVER
SCALE: 1:10

2 REF.2 DETAIL
SCALE: 1:10

4 REF.2 DETAIL
SCALE: 1:10

B REF.3 SECTION
SCALE: 1:10

C REF.3 SECTION
SCALE: 1:5

DRAWING NOTES:

1. PROVIDE FOUNDATION DOWEL AT EVERY REINFORCED WALL CORE LOCATION. EXISTING CONCRETE SHALL BE SCANNED PRIOR TO DOWEL INSTALLATION.
2. FASTEN 38x286 CONTINUOUS NAILER BOARD TO 38x140 CONTINUOUS NAILER BOARD WITH #10-76mm LONG WOOD SCREWS AT 300 O.C. 1 ROW AND 4 ADDITIONAL SCREWS AT EACH END.
3. SCAN CONCRETE SUBTRATE AND LAYOUT LEDGE ANGLE ANCHOR LOCATIONS TO AVOID INTERFERENCE WITH REBAR.

NO.	DRAWING NUMBER	REFERENCE DRAWING TITLE
10		
9		
8		
7		
6		
5		
4		
3	1-0162L-B0003-001	MAIN FLOOR & ROOF PLAN - NEW
2	1-0162L-B0005-001	BUILDING SECTIONS - NEW
1	1-0162L-B0004-001	ELEVATIONS - NEW

REFERENCE DRAWINGS

1000 0 1000 2000 3000 4000
SCALE: 1:50

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
KGS Group
No. 245

B.M.
ELEV.

NO.	REVISIONS	DATE (YY/MM/DD)	BY
0	ISSUED FOR CONSTRUCTION	2023 03 23	CMS

KGS GROUP

DESIGNED BY S. HILDEBRAND
CHECKED BY CMS
DRAWN BY S. HILDEBRAND
APPROVED BY CMS
SCALE: HORIZONTAL AS SHOWN
VERTICAL
RELEASED FOR CONSTRUCTION
DATE 2023 03 23
DATE

ENGINEER'S SEAL
PROVINCE OF MANITOBA
S. SUCHKOV
Member
34686
REGISTERED PROFESSIONAL ENGINEER
2023-03-23

CONSULTANT DRAWING NUMBER
22-0107-004_B11

Winnipeg
THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT
ENGINEERING DIVISION

METCALFE LIFT PUMPING STATION
2022 UPGRADES
BUILDING
WALL SECTIONS & DETAILS
NEW

CITY DRAWING NUMBER 1-0162L-B0006-001
SHEET 108 OF 109

PLOT DATE: 2023 03 23
BID OPPORTUNITY: 864-2022
FILE PATH: \\k-file-4\p-data\Projects\2022\22-0107-004\Dwg\Struct\