ROOM FINISH SCHEDULE

ROOM NO.	NAME	FLOOR MATERIAL	FLOOR FINISH	FLOOR BASE	NORTH WALL MATERIAL	NORTH WALL FINISH	EAST WALL MATERIAL	EAST WALL FINISH	SOUTH WALL MATERIAL	SOUTH WALL FINISH	WEST WALL MATERIAL	WEST WALL FINISH	CEILING MATERIAL	CEILING FINISH	CEILING HEIGHT	REMARKS
101	CONTROLS ROOM	EXIST/NEW CONC	EPOXY COATING	–	NEW CB	P	NEW CB	P	NEW CB	P	NEW CB	P	NEW PLYWD	P	3200	
SL1	SUB–LEVEL 1	CONC	–	–	EXIST CONC	–	EXIST CONC	–	EXIST CONC	–	EXIST CONC	–	EXIST CONC	–	±2692	
SL2	SUB–LEVEL 2	CONC	–	–	EXIST CONC	–	EXIST CONC	–	EXIST CONC	–	EXIST CONC	–	EXIST CONC	–	±2743	
SL3	SUB–LEVEL 3	CONC	–	–	EXIST CONC	–	EXIST CONC	–	EXIST CONC	–	EXIST CONC	–	EXIST CONC	–	±2251	

DOOR SCHEDULE ABBREVIATIONS

CB	CONCRETE BLOCK
CONC	CONCRETE
EXIST	EXISTING
P	PAINT
PLYWD	PLYWOOD

DOOR SCHEDULE

DOOR NO.	DOOR SIZE (WxHxT)	DOOR ELEV.	DOOR MAT'L.	DOOR CORE	DOOR FINISH	DOOR REMARKS	FRAME SECT.	FRAME MAT'L	FRAME FINISH	FRAME REMARKS	FIRE RATING (HOURS)	HARDWARE: HINGES	PANIC PUSH BAR	LOCK SET	PASSAGE SET	PRIVACY LOCK	PUSH/PULL	ELECTRIC STRIKE	CLOSER	DOOR STOP	FLUSH BOLTS	ASTRAGAL	WEATHERSTRIP	SWEEP	THRESHOLD	GLAZING	KICKPLATE	SIGN	REQUEST TO EXIT	DOOR CONTACT	CARD READER	SLIDE LOCKS	ELECT. OPERATOR	LOW HEADROOM TRACK	HARDWARE GROUP
D101	1200 x 2150 x 45	1A	HM	INSUL	P		A	PS	P	STEEL STIFFENED DOOR	–	●		●					●				●	●	●		●								1

DOOR SCHEDULE ABBREVIATIONS

HM	HOLLOW METAL
INSUL	INSULATED
P	PAINT
PS	PRESSED STEEL

DOOR HARDWARE

GROUP 1

QTY	DESCRIPTION	NUMBER	MFR
2	HINGES	TA 314 4 1/2"x4" NRP	McKINNEY
1	LOCKSET	AU5405LN x ASA (WITHOUT CYLINDER)	YALE
1	CLOSER	4041 CUSH	LCN
1	WEATHERSTRIP	W29 1/3 + 2/7	KN CROWDER
1	DOOR SWEEP	W24S	KN CROWDER
1	THRESHOLD	CT–76	KN CROWDER
1	KICKPLATE	K10Ax254mm	STANDARD METAL

DOOR ELEVATIONS

SCALE: 1:50

HEAD

JAMB

SILL

A

FRAME SECTIONS

SCALE: 1:10

NO.	DRAWING NUMBER	REFERENCE DRAWING TITLE
10		
9		
8		
7		
6		
5		
4		
3		
2		
1	–	–

REFERENCE DRAWINGS

1000 0 1000 2000 3000 4000

SCALE: 1:50

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
KGS Group
No. 245

B.M.
ELEV.

NO.	REVISIONS	DATE (YY/MM/DD)	BY
0	ISSUED FOR CONSTRUCTION	2023 03 23	CMS

KGS GROUP

DESIGNED BY S. SUCHKOV
CHECKED BY CMS
DRAWN BY F. VALENCIA
APPROVED BY CMS
SCALE: HORIZONTAL AS SHOWN VERTICAL
RELEASED FOR CONSTRUCTION
DATE 2023 03 23
DATE

ENGINEER'S SEAL
PROVINCE OF MANITOBA
S. SUCHKOV
Member 34686
REGISTERED PROFESSIONAL ENGINEER
2023-03-23

CONSULTANT DRAWING NUMBER
22–0107–004_B12

Winnipeg

THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT
ENGINEERING DIVISION

METCALFE LIFT PUMPING STATION
2022 UPGRADES
BUILDING
ROOM FINISH & DOOR SCHEDULE
NEW

CITY DRAWING NUMBER 1-0162L-B0007-001

SHEET 109 OF 109

PLOT DATE: 2023 03 23
BID OPPORTUNITY: 864-2022
FILE PATH: \\k-file-4\p-data\Projects\2022\22-0107-004\Dwg\Struct\