GENERAL NOTES:

1. PROVIDE DEMOLITION OF EXISTING HYDRO–OWNED SERVICE CONDUCTORS, SERVICE MAST AND UTILITY METER SOCKET. COORDINATE SERVICE SHUTDOWN WITH MB–HYDRO.
2. PROVIDE DEMOLITION OF EXISTING TELEPHONE LINE TO THE BUILDING. COORDINATE THE WORK WITH BELL MTS.
3. PROVIDE DEMOLITION OF ALL EXISTING ELECTRICAL EQUIPMENT AND CABLING WITHIN THE BUILDING AND ALL LOWER LEVELS.

LEGENDS:

EXISTING OVERHEAD TELEPHONE LINE

EXISTING OVERHEAD HYDRO LINE

PLAN

SCALE: 1:30

300 0 300 600 900 1200

SCALE: 1:30mm

NO.	DRAWING NUMBER	REFERENCE DRAWING TITLE

REFERENCE DRAWINGS

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
KGS Group
No. 245

B.M.
ELEV.

NO.	REVISIONS	DATE (YY/MM/DD)	BY
0	ISSUED FOR CONSTRUCTION	2023 03 24	DDW

KGS GROUP

DESIGNED BY	A. NIRMAL	CHECKED BY	DDW
DRAWN BY	R. GASPAR	APPROVED BY	DDW
SCALE: HORIZONTAL	NTS	RELEASED FOR CONSTRUCTION	
VERTICAL	NTS		
DATE	2022/11/30	DATE	

PLOT DATE: 2023 03 23

ENGINEER'S SEAL

PROVINCE OF MANITOBA
D.D. WILSON
Member
22552
2023-03-23
REGISTERED PROFESSIONAL ENGINEER

CONSULTANT DRAWING NUMBER
22–0107–004–E01.01

BID OPPORTUNITY: 864-2022

Winnipeg

THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT
ENGINEERING DIVISION

METCALFE LIFT PUMPING STATION
2022 UPGRADES
ELECTRICAL SITE PLAN
DEMOLITION

CITY DRAWING NUMBER 1–0162L–E0001–001

SHEET 53 OF 109

FILE PATH: P:\Projects\2022\22-0107-004\Dwg\Elec\
FILE NAME: 1-0162L-E0001-001.dwg