ALLEY NORTH OF METCALFE AVENUE (WEST OF ST MARY'S ROAD)

PLAN
SCALE: 1:50

KEYPLAN
SCALE: N.T.S.

BOLLARD DETAIL
SCALE: N.T.S.

NOTE:
1. ALL HARDWARE TO BE HOT DIPPED GALVANIZED.
2. WOOD FOR FENCE TO BE ACQ PRESSURE TREATED SPF COLOR: CEDAR TONE BROWN.

PARKING FENCE DETAIL
SCALE: N.T.S.

PAVEMENT STRUCTURE
SCALE: N.T.S.

GENERAL NOTES:

1. ALL WORKS TO BE IN ACCORDANCE WITH THE LATEST REVISIONS OF THE CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS.
2. CONTRACTOR TO VERIFY ALL EXISTING UNDERGROUND UTILITIES AND EXISTING SERVICES USING SOFT-DIGGING METHODS PRIOR TO CONSTRUCTION.
3. CONTRACTOR TO MARK ALL TREES FOR PRUNING AND/OR REMOVAL PRIOR TO CONSTRUCTION FOR REVIEW AND APPROVAL BY THE CONTRACT ADMINISTRATOR.
4. ANY WORKS AND/OR PERMITS ASSOCIATED WITH TEMPORARILY SUPPORTING, RAISING, AND/OR RELOCATING OVERHEAD POWER LINES AS REQUIRED TO FACILITATE THE WORK IS THE RESPONSIBILITY OF THE CONTRACTOR. CONTACT THE LOCAL MANITOBA HYDRO OFFICE TO ARRANGE FOR MANITOBA HYDRO STAFF TO LIFT POWER LINES, TEMPORARILY SUPPORT UTILITIES, AND/OR RELOCATE UTILITIES. ONLY MANITOBA HYDRO STAFF WILL BE PERMITTED TO LIFT POWER LINES.

ENGINEERS GEOSCIENTISTS MANITOBA
Certificate of Authorization
KGS Group
No. 245

0.0 2.0 4.0 6.0

METRIC
WHOLE NUMBERS INDICATE MILLIMETRES
DECIMALIZED NUMBERS INDICATE METRES

WARNING

IF POWER EQUIPMENT OR EXPLOSIVES ARE TO BE USED FOR EXCAVATION ON THIS PROJECT THE CONTRACTOR MUST:

1) NOTIFY THE GAS COMPANY OF THE PROPOSED LOCATION OF EXCAVATION.

2) TAKE PRECAUTION TO AVOID DAMAGE TO GAS COMPANY INSTALLATIONS.

SEE PROVINCIAL REGULATION 210/72 FOR DETAILS

LOCATION APPROVED
UNDERGROUND STRUCTURES

SUPV. U/G STRUCTURES COMMITTEE — DATE

NOTE:

LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

B.M.
ELEV.

NO.	REVISIONS	DATE	BY
0	ISSUED FOR CONSTRUCTION	2023 03 24	RBO

KGS GROUP

DESIGNED BY	NGV	CHECKED BY	RBO
DRAWN BY	GEL	APPROVED BY	RBO
SCALE: HORIZONTAL	1:50	RELEASED FOR CONSTRUCTION	
VERTICAL	–		
DATE	2023 03 24	DATE	

PLOT DATE: 2023 03 24

ENGINEER'S SEAL
PROVINCE OF MANITOBA
2023-03-24
R. B. OFFMAN
Member
22701
REGISTERED PROFESSIONAL ENGINEER

CONSULTANT DRAWING NUMBER
22-0107-004-D03

BID OPPORTUNITY: 864-2022

Winnipeg

THE CITY OF WINNIPEG
WATER AND WASTE DEPARTMENT
ENGINEERING DIVISION

METCALFE LIFT PUMPING STATION
2022 UPGRADES
SITE PLAN

SHEET 3 OF 109

CITY DRAWING NUMBER
1-0162L-D0003-001

FILE PATH: P:\Projects\2022\22-0107-004\Dwg\Mun\
FILE NAME: 22-0107-004_CALL.dwg