



- CONSTRUCTION NOTES**
- REMOVE EXISTING ASPHALT
 - CONSTRUCT NEW ASPHALT OVERLAY (+/- 80mm)
 - REMOVE EXISTING PAVEMENT AND CONSTRUCT NEW 150mm REINFORCED CONCRETE PAVEMENT
 - REMOVE EXISTING CURB AND CONSTRUCT NEW BARRIER CURB (SD-205)
 - INSTALL NEW CATCH PIT WITH CURB AND GUTTER INLET FRAME (SD-023), AND CONNECT TO EXISTING CATCH BASIN WITH 250mm PVC PIPE AS PER CW 2130
 - CONSTRUCT NEW 100mm CONCRETE SIDEWALK (SD-228A)
 - RENEW EXISTING 100mm CONCRETE SIDEWALK (SD-228A)
 - CONSTRUCT NEW CURB RAMP (SD-229E)
 - INSTALL NEW FRAME AND SOLID COVER (AP-006, AP-007)
 - INSTALL LIFTER RING AND MATCH TO GRADE
 - CONSTRUCT NEW MODIFIED BARRIER CURB (SD-203B)
 - GRIND TREE STUMPS
 - REMOVE EXISTING APPROACH AND CONSTRUCT NEW 200mm REINFORCED CONCRETE APPROACH
 - RENEW EXISTING ASPHALT WALK
 - ABANDON EXISTING CATCH PIT AS PER CW 2130
 - ABANDON EXISTING CURB INLET AS PER CW 2130

- GENERAL NOTES**
- PAVEMENT DIMENSIONS ARE TO BACK OF CURB
 - ALL CURB RADII UNDER 15.0m SHALL BE MODIFIED
 - CURB REPLACEMENT AS DIRECTED BY CONTRACT ADMINISTRATOR
 - INSTALL DETECTABLE WARNING TILES AS DIRECTED BY CONTRACT ADMINISTRATOR (CW 3326)
 - PAVEMENT REPAIRS SHOWN ARE ONLY A REPRESENTATIVE SAMPLE OF THE TENDERED QUANTITIES
 - ASPHALT TIE-INS ON APPROACHES TO BE DETERMINED IN THE FIELD BY THE CONTRACT ADMINISTRATOR
 - ADJUST WATER VALVES, HYDRANT ASSEMBLIES AND WATER SERVICE SHUT-OFF VALVES TO GRADE IF REQUIRED
 - CONTRACTOR TO CONFIRM THE LOCATION OF ALL UTILITIES / SERVICES IN THE FIELD PRIOR TO CONSTRUCTION

FOR TENDER PURPOSES ONLY
NOT FOR CONSTRUCTION

METRIC
WHOLE NUMBERS INDICATE MILLIMETERS
DECIMALIZED NUMBERS INDICATE METERS

TENDER NO. 1-2023

EXISTING	LEGEND - PLAN	PROPOSED	EXISTING	LEGEND - PLAN	PROPOSED	EXISTING	LEGEND - PROFILE	PROPOSED
⊕	HYDRANT	◆	---	LDS/WWS	---	□	UTILITY BOX	□
⊗	VALVE	●	---	WATERMAIN	---	○	UTILITY MAN HOLE	○
⊖	CURB STOP	●	---	GAS	---	▨	CONCRETE	▨
○	MANHOLE	●	---	TRAFFIC SIGNALS	---	▨	CONCRETE SIDEWALK	▨
□	CATCH BASIN	●	---	HYDRO/STREET LIGHT	---	▨	ASPHALT	▨
△	CURB INLET	■	---	MTS/SHAW	---	▨	LEGEND - PLAN	▨
○	HYDRO POLE	◆	---	CURB RENEWAL	---	▨	WEST GUTTER	▨
○	LIGHT STANDARD	◆	---	PROPERTY LINE	---	▨	CENTER LINE	▨
○	TRAFFIC SIGNAL POLE	◆	---	RAMP CURB	---	▨	EAST GUTTER	▨
⊕	SURVEY BAR	◆	---	ELEVATIONS	(31.000)	▨	FENCE	▨
⊕	GEODETIC BENCH MARK	◆	---	TREES	---	▨		▨

LOCATION APPROVED	IB @ NE CORNER OF BUNTING & CHURCH	B.M. ELEV.
UNDERGROUND STRUCTURES	231.812	
SUPR. U/G STRUCTURES		
DATE		

NOTE:
LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE. BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

ENGINEERING DIVISION	TECHNOLOGY SERVICES BRANCH	106 - 1155 PACIFIC AVE
DESIGNED BY	T.G.	CHECKED BY
DRAWN BY	T.G.	APPROVED BY
HOR. SCALE	1 : 250	DATE
VERTICAL	1 : 10	2023/03/13

NO.	REVISIONS	DATE	BY
3.	ADDENDUM 1	23/03/14	M.F.
2.	ISSUED FOR TENDER	23/03/07	M.F.
1.	SUBMIT FOR PLAN APPROVAL	23/01/31	T.G.

THE CITY OF WINNIPEG
PUBLIC WORKS DEPARTMENT

2023 LOCAL STREET RENEWAL PROGRAM
BUNTING STREET
FROM CHURCH AVENUE TO INKSTER BOULEVARD
CONCRETE REHABILITATION WITH ASPHALT OVERLAY AND ASSOCIATED WORKS
FROM STA. 4+60 TO STA. 5+80

CITY DRAWING NUMBER SE-23-42
SHEET 10 OF 26
4