MATERIAL NOTES

1. ALL WORK TO CONFORM TO CURRENT CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS AND DETAILS UNLESS OTHERWISE NOTED.
2. DIMENSIONS ARE IN METERS UNLESS OTHERWISE NOTED.
3. DO NOT SCALE DRAWING.
4. PROTECT EXISTING TREES TO REMAIN, TYP.
5. DAMAGES TO EXISTING SOD BEYOND WORK AREAS INDICATED ON DRAWINGS SHALL BE THE REPONSIBILITY OF THE CONTRACTOR TO RESTORE AS PER CITY OF WINNIPEG STANDARDS UNLESS OTHERWISE APPROVED BY CONTRACT ADMINISTRATOR.

LEGEND

1. Supply and Install Compacted Granular Path as per SCD-646 (Hatched Area, 470 SM)
2. Pickup and Install Composite Backed Benches as per SCD-121A (3)
3. Pickup and Install Double-Sided Park Sign (2)
4. Existing Concrete Pathway

Park Property Line

LS Existing Light Standard

0 10 15 20 m

N

CONTRACTOR TO CONFIRM ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION. LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

Winnipeg

THE CITY OF WINNIPEG
Planning, Property and Development Department
Planning and Land Use Division
Unit 15 - 30 Fort Street, Winnipeg, MB, (R3C 4X5)

DESIGNED BY		CHECKED BY	
DRAWN BY	MG	APPROVED BY	
HORIZ. SCALE	1:300		
VERT. SCALE			
DATE	January 2023		

MANAGER, PARK AND OPEN SPACES — DATE

MANAGER, PLANNING AND LAND USE DIVISION — DATE

DRAWING TITLE
Hiddleston Park
Playground Redevelopment
Materials Plan C

SITE ADDRESS 38 Hiddleston Cres.

DRAWING NO.
H.32-C4

BID OPPORTUNITY NO.
108-2023

06-01-23 Template.mcd Monday, January 23, 2006