DEMOLITION & REMOVALS NOTES

1. ALL WORK TO CONFORM TO CURRENT CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS AND DETAILS UNLESS OTHERWISE NOTED
2. DIMENSIONS ARE IN METERS UNLESS OTHERWISE NOTED
3. DO NOT SCALE DRAWINGS
4. PROTECT EXISTING TREES TO REMAIN, TYP.
5. SECURE CONSTRUCTION SITE AND STAGING AREA WITH CONSTRUCTION FENCING C/W SAFETY SIGNAGE
6. CONFIRM STAGING AREA W/ CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION.

LEGEND

1. Remove Existing Swing Set, Play Equipment, Timber Edging, Bench and Waste Receptacle
2. Excavate and Remove Existing Peastone and Earthen Materials within New Play Area to Required Depth for Engineered Wood Fibre Safety Surfacing (Blue Area, 77 CM).
3. Excavate and Legally Dispose of Existing Peastone and Earthen Materials outside of New Pathways and Play Area to a min of 200 MM (15 CM).
4. Excavate as Required for New Gravel Path (470 SM)
5. Remove Existing Shrubs (Red Dashed Line, 7 Shrubs)
6. Existing Post and Chain Fencing to Remain

Extents of New Play Area and Pathway

—SM— Sewer Main —WM— Water Main Park Property Line

LS Existing Light Standard to Remain

Trees Indicated with Red Circles to be Protected with Strapping (15)

CONTRACTOR TO CONFIRM ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION. LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

Winnipeg

THE CITY OF WINNIPEG
Planning, Property and Development Department
Planning and Land Use Division
Unit 15 - 30 Fort Street, Winnipeg, MB, (R3C 4X5)

DESIGNED BY		CHECKED BY	
DRAWN BY	MG	APPROVED BY	
HORIZ. SCALE / VERT. SCALE	1:250		
DATE	January 2023		

MANAGER, PARK AND OPEN SPACES — DATE

MANAGER, PLANNING AND LAND USE DIVISION — DATE

DRAWING TITLE
Hiddleston Park
Playground Redevelopment
Existing Conditions and Removals

SITE ADDRESS 38 Hiddleston Cres.

DRAWING NO.
H.32-C1

BID OPPORTUNITY NO.
108-2023

06-01-23 Template.mcd Monday, January 23, 2006