MATERIAL NOTES

1. ALL WORK TO CONFORM TO CURRENT CITY OF WINNIPEG STANDARD CONSTRUCTION SPECIFICATIONS AND DETAILS UNLESS OTHERWISE NOTED.
2. DIMENSIONS ARE IN METERS UNLESS OTHERWISE NOTED.
3. DO NOT SCALE DRAWING.
4. PROTECT EXISTING TREES TO REMAIN, TYP.
5. DAMAGES TO EXISTING SOD BEYOND WORK AREAS INDICATED ON DRAWINGS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO REPAIR AND MAKE GOOD AS PER CITY OF WINNIPEG STANDARDS UNLESS OTHERWISE APPROVED BY CONTRACT ADMINISTRATOR.

LEGEND

1. Supply and Install 8' Tall Two-Bay Swing Set w/ 2 Belt Seats and 2 Bucket Seats
2. Supply and Install Age 2-12 Play Equipment (Dashed Blue Line, 133 SM)
3. Supply and Install Engineered Wood Fibre Safety Surfacing as per SCD-650 (Hatched Area, 248 SM)
4. Supply and Install Two-Tier Timber Edging as per SCD-651A (67 LM)
5. Supply and Install Accessible Entrance as per Detail 1/H.32-C5
6. Supply and Install Compacted Granular Path as per SCD-646 (Hatched Area, 470 SM)
7. Supply and Install Picnic Tables (1 Regular, 1 Accessible) as per SCD-122 and SCD-122A
8. Supply and Install Composite Backed Benches as per SCD-121A (3)
9. Supply and Install Subsurface Drainage to Emitter as per SCD-659/ SCD-661. Exact location to be determined on site.
10. Supply and Install Topsoil and Sod (Hatched Area, 360 SM)
11. Supply and Install Curb Cut and Accessible Concrete Approach as per SD-229C/SCD-662 (Hatched Area, 7 SM)
12. Supply and Install Waste Receptacle as per SCD-119 (1)
13. Supply and Install Double-Sided Park Sign (2)

SM — Sewer Main
WM — Water Main
Park Property Line
LS Existing Light Standard

CONTRACTOR TO CONFIRM ALL DIMENSIONS AND REPORT ANY DISCREPANCIES TO CONTRACT ADMINISTRATOR PRIOR TO CONSTRUCTION. LOCATION OF UNDERGROUND STRUCTURES AS SHOWN ARE BASED ON THE BEST INFORMATION AVAILABLE BUT NO GUARANTEE IS GIVEN THAT ALL EXISTING UTILITIES ARE SHOWN OR THAT THE GIVEN LOCATIONS ARE EXACT. CONFIRMATION OF EXISTENCE AND EXACT LOCATION OF ALL SERVICES MUST BE OBTAINED FROM THE INDIVIDUAL UTILITIES BEFORE PROCEEDING WITH CONSTRUCTION.

Winnipeg

THE CITY OF WINNIPEG
Planning, Property and Development Department
Planning and Land Use Division
Unit 15 - 30 Fort Street, Winnipeg, MB, (R3C 4X5)

DESIGNED BY		CHECKED BY	
DRAWN BY	MG	APPROVED BY	MANAGER, PARK AND OPEN SPACES — DATE
HORIZ. SCALE / VERT. SCALE	1:300		
DATE	January 2023		MANAGER, PLANNING AND LAND USE DIVISION — DATE

DRAWING TITLE
Hiddleston Park
Playground Redevelopment
Materials Plan A

SITE ADDRESS 38 Hiddleston Cres.

DRAWING NO.
H.32-C2

BID OPPORTUNITY NO.
108-2023

06-01-23 Template.mcd Monday, January 23, 2006